



LONG RANGE PLANNING COMMITTEE

Chair: Roger Gatlin

Vice Chair: John Fitzgibbon

Secretary/Treasurer: George

Dubois

George Roat

Lloyd Woosley

Frank Krens

Gregg Anderson

Council Liaison: Molly Rose

Agenda

Agenda

January 26, 2023

6:00 PM

TOWN HALL

520 MAIN STREET

WINDERMERE, FL 34786

PLEASE TURN OFF ALL CELL PHONES AND PAGERS

PLEASE NOTE: IN ACCORDANCE WITH F.S. 286.26: Person with disabilities needing assistance to participate in any such proceedings should contact the Office of the Clerk at least 48 hours beforehand at (407) 876-2563.

Pursuant to Resolution No. 2005-12 adopted on December 13, 2005, the following Civility Code shall govern all proceedings before the Town of Windermere Long Range Planning Committee:

1. All electronic devices, including cell phones and pagers, shall be either turned off or otherwise silenced.
2. Prolonged conversation shall be conducted outside Council meeting hall.
3. Whistling, heckling, gesturing, loud conversations, or other disruptive behavior is prohibited.
4. Only those individuals who have signed the speaker list and/or who have been recognized by the Mayor (or Chair) may address comments to the Council.
5. Comments at public hearings shall be limited to the subject being considered by the Council
6. Comments at Open Forums shall be directed to Town issues.
7. All public comments shall avoid personal attacks and abusive language
8. No person attending a Long Range Planning Committee meeting is to harass, annoy, or otherwise disturb any other person in the room.

Any member of the public whose behavior is disruptive and violates the Town of Windermere Civility Code is subject to removal from the Long Range Planning Committee meeting by an officer and such other actions as may be appropriate. PLEASE NOTE: IN ACCORDANCE WITH F.S. 286.0105: Any person who desires to appeal any decision at this meeting will need a record of this proceeding. For this, such person may need to ensure that a verbatim record of such proceeding is made which includes the

AGENDA

1. THE MEETING IS CALLED TO ORDER BY THE CHAIR

2. OPEN FORUM / PUBLIC COMMENT (3-Minute Limit)

3. NEW BUSINESS

a. Minutes

i. Long Range Planning Committee Virtual Workshop Minutes - May 19, 2022
(Attachment - Board Option)

b. Projects

- i. Review List of Current Town Projects (Attachment)
- ii. Rotary / Healthy West Orange Pavilion (Attachment)

4. ADJOURN

May 19, 2022 LRP Virtual Workshop

Draft Minutes

Meeting Called to Order 6pm

Present: Roger Gatlin, John Fitzgibbon, George Dubois, Frank Krens, Gregg Anderson, and Council Liaison Molly Rose

Absent: George Roat and Lloyd Woosley

Motion made by Gregg Anderson to close all street access points on the southerly side of 6th Ave. From Oakdale Street to 7th Ave. Also, to close the access at 12 Ave. and S. Main St. Frank Krens seconded the motion. All voted in favor.

Adjourn 7:29pm

January Projects Meeting

For previous updates on each item please refer to December projects meeting minutes

Attendees:

- Robert Smith, Town Manager
- 1. Tonya Elliott-Moore, Public Works Director Town of Windermere
- John Fitzgibbon, Town of Windermere
- ~~Nora White, Finance Director, Town of Windermere~~
- Travis Mathias, Town of Windermere - Not in Attendance
- Tony Davit, Town Councilman Liaison
- Mike Woodward, Kimley-Horn Associates - Not in Attendance
- Hao Chau, Kimley-Horn Associates
- Victor Gallo, Kimley-Horn Associates - Not in Attendance
- Mike Galura, Michael Galura Engineering Consultants

1. **NPDES (National Pollutant Discharge Elimination System):** *The NPDES permit program addresses water pollution by regulating point sources that discharge pollutants to waters of the United States.* Since the Town discharges into the lakes we are required to maintain this permit. 10/18: MBG addressed additional comments for NOI and Annual Report. Per conversation with Jason Maron, response to audit is complete. Awaiting completeness and acceptance letter. Issuance of NOI, Cycle 4 pending. MBG will distribute forms to be used for compliance (i.e., fleet maintenance, erosion/sedimentation control, etc.). Community project scheduled for Saturday, November 3rd (clean-up on lakefront, etc.) per Scott Brown. Final reading for ordinance scheduled for November 13th TC meeting. TM to coordinate with Da'Shanta and Diane on distributing Stormwater pamphlets with Boat Ramp Keys. TM reached out to BC and PDCS as well. Town received additional comments for NOI from Jason Maron. MG to address and resubmit. Comments are minor – MG to try to have responses by next week. MG to work on additional stormwater related brochures for rack in front of receptionist desk. MG coordinate with Diane on Gazette articles and number of Gazettes' issued. MG to provide Town with public education brochures for front magazine rack. Mike had DEP public notice published in February 10, Sunday edition of Orlando Sentinel. Inquiries to be made to Jason Maron, FDEP. Expecting NOI to be issued this month. MG contacted Jason Maron, DEP, for status of pending NOI. Received violation by residential builder. Coordinate with Dianne on Gazette on stormwater related articles. Awaiting Notice of Public Petition to be published in Orlando Sentinel (to be published this Saturday). Once published, need to forward proof of publication to Jason Maron, FDEP. Proof of Publication for Public Petition from Orlando Sentinel forwarded to Jason

Maron, FDEP. Issuance of NOI Cycle 4 pending (permit issued May 3, 2019). KH to pick up NPDES tasks from MG based on KHA being selected as Town Continuing Consultant. KHA will prepare NPDES brochure and in-house training schedule. MG to send SOP's to HC for NPDES compliance. HC to prepare brochure for stormwater related subjects. Articles to also be published in quarterly Gazette. Violations being documented. HC to prepare stormwater related articles for the quarterly Gazette. Training is will also be initiated (late March and before Memorial Day for Town employees). Subject will range from illicit discharge to stormwater and sediment control. HC preparing for FDEP audit. Jason Maron, FDEP, to be in Town 10/24 to review Town NPDES program. KHA will be working on Gazette article for next publication. SB to provide deadline for submittal. Monthly sweeping and documentation will continue. Two (2) violations noted by JF and coordinated with BC of Wade-Trim. KHA working on Illicit Discharge power-point presentation, scheduled for March/April 2020. Draft of presentation to be provide to TM and SB in November. SB and KHA attended FDEP audit. SB and KHA to continue to coordinate with NPDES staff to provide documentation and forms. Supply KHA with street sweeping and vacuum truck quantities. Submitted article for Gazette. First training in March to include documentation forms. SB spoke to EnviroServices to map drainage infrastructure. HC coordinating with SB on street sweeping and drainage structure debris quantities. March training HC. KHA and SB addressing FDEP questions noted in their Ph II MS4 Cycle 4 Year 1 Focused Audit Report. Reply to be completed by March 2, 2020. ON schedule. Moving forward with Town stormwater inventory via CCTV all systems (to set the control point), GPS and building mapping system for recording, reporting and monitoring current and future needs/cleanings, etc. This will be a team effort through KHA, Enviro Waste Services and SB. Debris removals being recorded via HC. 2/3: HC provided MG with quantities for street sweeping. MG to include with STAR report to DEP. SB to provide estimate to TM for decanting of dewatering. SB to also work with Vacuum trucks to identify GPS locations and quantities per GPS location to monitor any issues. Article has been submitted for Gazette. KHA and SB has responded to FDEP questions on focused audit. Vacuum truck services have completed GPS and CCTV work at 12th Street and Oakdale. KHA and SB to work on how to get this information into GIS. Potential dates for training in April. Training slides sent to SB for approval (slides approved). Training session to be scheduled. First set of inlets from truck vac for inventory. Proposal to incorporate vacuum information. Tentative training to be conducted in July-August. Two sessions: 1) Public Works and 2) Police Department. SB to coordinate with Chief on scheduling training. HC to submit projected budget impacts for next FY. Gazette articles submitted. Vac trucks working on drainage structure inventory. All training material prepared per HC. Year 2 reporting due by June 2021 – may defer training until COVID-19 restrictions are eased. Thursday nights are best for training with PD per TM. HC and SB to coordinate on when the training can be conducted (for all Town Staff). KHA agreement approved at last TC meeting. Inspection for 505 and 1108 Dirt Main sent out by JF (now in compliance) for noncompliance. IPO approved. Documentation continuing for vac truck. Need to schedule 2 training sessions with staff (PD and Public Works). SB suggested a virtual training session. HC to provide copies of training documents and to coordinate with SB on dates of training sessions. Staff training dates scheduled. Training Sessions completed (October 2020). KHA working on standardized violation forms. 12/7/20 - Prepare standard violation forms. MG will send to HC. No reporting to DEP required till next year (Year 2 reporting). 1/6/21 Ongoing. 2/1/21 Additional reports received and filed. 3/1/21 Draft – List for violations to be sent out to the Town for review. 5/3/21 Next report in October-November. HC working on violation forms to TC for review. Violations noted by JF and BC in Rosser Reserve. Violations documented by JF. Training will be taped and added to Power DMS. 6/7/21 NPDES budget provided to TC from HC. TM coordinating with PD to train Officers. 7/12/21 KHA tracking vacuum and street sweeping. MG to coordinate with HC on inventory (see previous e-mail from HC). Training sessions completed. JF reported 2 violations' that have since been resolved. Continue tracking NPDES items. 9/13 Ongoing tracking. Annual report due in November. 10/4 Ongoing tracking. Annual report due in November. 12/6/21 Annual report has been submitted. Received RAI and will respond. 1/10/22 Annual report submitted and

approved. 2/14/22 – Ongoing, public outreach via social media, lake cleanup on 2/20. 3/7 Lake cleanup well received. Another lake cleanup scheduled for 3/27. Social media platforms Facebook and Instagram. Town will look to have a clean-up quarterly. TEM provided quantities for NPDES compliance/info. 4/4/22 Submitted Biennial Report and documenting for the annual report. 3/7 and 3/27 lake cleanup conducted by the Town. TEM to document cleanup efforts and quantities to HC. 5/2 NPDES violations noted at 10988 Down Yonder Lane. BC working with owner on resolution of violation. TM Spoke to Brad and issue resolved. JF to note issue on Oakdale 6/6 vacuum and sweeping amounts provided to KHA for reporting purposes. 7/11 Ongoing. HC compiling data from vacuuming and cleaning. 8/1 - Ongoing compiling and documenting. 9/12 Ongoing – Violation 10/10 – Ongoing – violations documentation. 11/7 Ongoing – no violations reported. 12/5 – Ongoing – Hurricane prep emails documented. **1/09 - Ongoing.**

2. Orange County LMS: Orange County Local Mitigation Strategy (LMS) is comprised of the County and other governmental jurisdiction within it to plan and prepare for natural disasters. These projects are funded by FEMA. FEMA has dedicated \$15 million to the County to fund various projects. TOW has submitted 7 projects for funding including W Second Ave. This is a 25% match program. The process takes about 2 years. 10/18: MBG ask Jason Taylor for status. MG to review comments for 5 HMGP projects from DEM (Douglas Galvan) and address within 15-days for 5 projects. MG to resubmit by DEM timeline. MG resubmitted revised Pre-Disaster application for funding of Preliminary Engineering for West Second Avenue. Geotechnical and Surveying services were not eligible because the services were performed before the Hurricane Irma disaster declaration. Awaiting word on technical review of HMGP applications. Update on Hurricane Irma HMGP applications (contact Douglas Galvan on status update). LMS Working Group Meeting scheduled for later in May (May 22nd). Jason Taylor encouraged the submittal of applications for Tier 3 projects under Hurricane Michael disaster declaration. JT feels that there will be substantial money available due to rural and smaller communities in the Panhandle not being able to provide matching funding sources for HMGP applications. MG to notify JT of budget change for West Second Avenue for Preliminary Engineering. KHA to work on Hurricane Michael applications (due August). MG to continue on Hurricane Irma tasks. MG to address comments from Mitchell Plummer, Engineering Specialist, Mitigation Bureau, Florida Division of Emergency Management by 07/12/2019. These projects are:

- 4337-693: 3rd Avenue and Magnolia Street Drainage Improvements;
- 4337-694: 6th Avenue and Butler Street Drainage Improvements; and
- 4337-695: 9th Avenue/10th Avenue and Oakdale Street Drainage Improvements
- 4337-697: West Second Avenue TM executed agreement and it was sent back to DEM for their execution and authorization to proceed with the Phase I design services.

DEM is reviewing the technical/engineering aspects of these projects for eligibility, feasibility and cost-effectiveness.

MG to attend LMS meeting on Wednesday August 21st at Orange County OEC (10:00 am). MG mentioned money may be available under Tier 3 funding for Hurricane Michael. Town to consider projects.

MG is to submit an HMGP for the Lake Down retaining wall under Hurricane Michael. Project will only be eligible under Tier 3 money. Applications considered by the State (DEM) is on a first come, first serve basis.

MG continuing to prepare HMGP application for the Lake Down retaining wall improvements under Hurricane Michael. MG to e-mail DEM engineers for application status for Hurricane Irma. MG re-submitted Lake Down Wall Improvement project to Daniel Negron, P.E., Orange County Public Works, for consideration by the Planning Committee for endorsement.

Initial approval for West Second Avenue Phase I Design with funded budget of \$80,000. After Phase I is complete then Phase II for Construction will begin. Estimated total cost is \$900,000 for both phases. Still waiting to hear back on other 3 projects.

Administration change at the Orange County LMS. Jason Taylor no longer LMS Manager.

Executed contract. Waiting on FEMA to sign. MG to revise scope and TM to work on title search for end of Second Avenue and easement. Public workshops will be included again. 18 months since last meeting. 2/3 MG prepared first quarterly report to Douglas Galvan, DEM (September-December 2019). Final design for West Second Ave to be on TC agenda for February 2020 meeting. MG emailed LMS and received RAI for two projects. MG to respond by /10 deadline.

MG submitted FEMA-4399-DR-FL HMGP application for Lake Down Retaining Wall to Kathleen Marshall, FDEM, Mitigation Bureau, on February 25, 2020. Project will be considered for Tier 3 funding under Hurricane Michael.

MG address environmental comments from DEM regarding applications 4337-693 (3rd Avenue and Magnolia Street) and 4337-694 (6th Avenue and Butler Street). The comments were from Kayla Born, FDEM. Two projects were considered ineligible for HMGP funding by the FDEM. These projects are 4337-695 (9th/10th Avenue and Oakdale Street) and 4337-696 (9th Avenue and East Boulevard Regional Stormwater Pond). RS mentioned infrastructure stimulus package may have money available for CIP's.

Received notification from DEM (Douglas Galvan) that Project 4338-443-R (693) 3rd Avenue and Magnolia Street Drainage – Phase I (Design and Permitting) has been approved for funding under the Hazard Mitigation Grant Program (HMGP). The Project Total Cost under Phase I: \$72,500; Federal Share: \$54,375; Local Share: \$18,125. The contract with DEM will be forthcoming for the Town's execution.

Reimbursement Request No. 1 processed by the DEM. Additional information submitted to Claudia Purser, DEM regarding 9th/10th and Oakdale and 9th/East Boulevard Regional Stormwater Pond. MG to follow up with Claudia on status of additional information. MG to prepare and submit quarterly report and Reimbursement Request No. 2 by the first week in July.

Second quarter reports sent to TM for his digital signature. Awaiting execution of two new project contracts with DEM.

New quarterly reports forms prepared and executed by the TM for the three (3) Town project – 4337-297-R (West Second Avenue); 4337-443-R (3rd Avenue and Magnolia Street); and 4337-449-R (6th Avenue and Butler Street) and submitted to Douglas Galvan, FDEM. All contracts executed and quarterly reports submitted. MG submitted an exhibit locating the three projects on a single Location Map to Paola Sullivan, DEM. Attended LMS Working Group meeting last month to discuss LMS projects and any other topics. Discussions on residential safe room funding. Manny Soto (City of Orlando) – Steering Committee chair; Daniel Negron (Orange County Stormwater Management Division) – Planning Committee chair. HC to provide typical section for 7th and Butler Street. Workshops and public meetings scheduled in October. Typical will be applied. Contract for three projects pending from

DEM (FEMA Project No. 4337-443-R). HC submitted quarterly report for three projects (contract pending). 11/2/20 Contract for three projects pending from DEM. HC submitted quarterly report for three projects (contracts pending). 12/7/20 - TM provided brief discussion regarding CCNA as it relates to procurement of the HMGP grants. TM had discussions with Gray-Robinson. TM to have 2nd zoom meeting with Gray-Robinson 12/8/20. 1/6/21 Bessie and Butler has been RFQ. Due on 1/11. 2/1/21 West 2nd received first reimbursement for design and proceeding with Bessie and Butler. Bessie/Butler RFQ to be approved at February TC Meeting. MG to contact DG and get confirmation of extensions. 3/1/21 Butler extension received. DEM agreement for Bessie, extension for Bessie. AIA agreements with KHA executed. 5/3/21 Extensions issued by DEM (Douglas Galvan) for Bessie and Oakdale. BC is working with FEMA on any ordinance changes. 6/7/21 LMS meeting scheduled for Wednesday, June 9th at 10:00 am – 12:00 am. All extensions from FDEM received. 7/12/21 HC and MG working on quarterly requests and reimbursement packages to Doug Galvan, FDEM. RS and TEM to look at other projects under other funding opportunities (September 1st deadline) with a minimum of \$2M. 8/9 All reports submitted. 9/13 MG attended LMS meeting. Meeting focused on upcoming update of County's LMS program and any changes that may need to be done. Doug Galvin is leaving and we are waiting on who will be next point of contact. 10/4 New contact is Brianna Nelson. KH and Galura to work on quarterly reports. 12/6/21 Next quarterly report is for period ending on 12/31. KH and Galura to prepare quarterly reports. Designs to be submitted by end of year and bids projected in January. Design Reimbursements to be submitted as well for last quarter. 1/10/22 DEM is updating project list and policies and will send to Michael Galura. Mike will send to Town staff. February agenda will ask for Resolution adopting policies and procedures. 2/14/22 Resolution to adopt Orange County LMS presented to February TC. Resolution approved 5-0. MG sent signed copy of resolution to John Mulhall, Orange County LMS Administrator. MG attended quarterly LMS meeting (virtual). FDEM was speaker and provided updates to LMS procedures and other applications. 3/7/22 MG to touch base with John Mulhall on acknowledgement of approval of resolution. Meeting on 3/8 to go over priorities and future funding. Staff to attend. 4/4 4th and Magnolia potential project. MG to ask John Mulhall about getting project on LMS list. 5/2 LMS meeting on May 11th at 10:00 am (Microsoft Teams meeting) Tonya or TM to attend. Include Nora on project numbers. Need reimbursables submitted. JF and TEM to submit application for 4th and Magnolia project 6/6 May 11th meeting was cancelled. Waiting for rescheduled meeting to address any additional projects. 7/11: Awaiting new Meeting. 8/1 - meeting scheduled on 8/10. 9/12 – MG sent forms to TEM on any potentially new projects to be considered for LMS funding (under disaster declaration). 10/10 – Federal disaster declaration expected for Orange County. 11/7 – MG to coordinate with HC on 4th and Magnolia future project. 2 other projects to be presented (retaining wall improvements) – 6th and Lake Down, 5th and Lake. 12/5 – LMS meeting postponed. MG to submit on two structural projects. Third project is 4th and Magnolia at Lake Down Park. FEMA will prioritize projects for Hurricane Ian. 1/09 - Waiting to hear back from FEMA. MG to follow up. Potential projects are two wall projects at 5th and Lake and 6th and Boat Ramp and one drainage project at 4th and Magnolia.

3. FIRST Avenue and FOREST Street Drainage Improvements: Grant awarded to TOW to address flooding within the Basin. 10/18: MBG awaiting all cancelled checks to prepare reimbursement form to SFWMD (Nestor Garrido). No further complaints on the project. Town is monitoring system for condition and adjust as needed per TC directive. Vacuuming service RFP sent out by SB. Bid opening November 8th at 3:00 pm at Town Hall. MG to still look at possibility of covering grates on roadway. MG submitted initial request for reimbursement. SFWMD responded and needs unique Town invoice number to process request. Debbie Wilson provided MG with unique Town invoice number. MG resubmitted invoice to Nestor Garrido. Town received \$175,000 reimbursement from the SFWMD. Project Complete. MG to review alternatives to grates in lieu of Mack Concrete's recommendation to cut inlet top and precast top with manhole frame and cover. Potential filter per JF – test site. Further evaluate grates on First Avenue on

whether to cap or maintain. MG to apply for DAC Recovery funding from DEM. \$31,564.07 is requested for DAC funding. MG to work to submit next week. DAC application submitted to Amanda Campen, Florida DEM, Bureau Chief of Recovery, 2555 Shumard Oak Boulevard, Tallahassee, Florida 32301 on July 1st, 2019. MG to follow up on submittal. KHA to review drainage system and provide Induvial Project Order (IPO) for recommendations and possible upgrades. Data collection for project fix. MG provided topographic information to SB per resident request. Project completed; reimbursement received. KHA to address additional concerns regarding project improvements. IPO released to KHA on analyzing alternatives to maintain stormwater within the Town right-of-way. HC to provide summary to TM. Draft Report to be submitted to TM and SB by Monday 10/7. KH submitted draft report to TM and SB. TM and SB have reviewed and have no comments. KH to submit final report with opinions of probable construction costs. HC reviewed DRAFT report which will be revised and submitted to SB for review. TC meeting on 12/18 for discussion of the report. Final report submitted by HC to TM and SB. Workshop with TC scheduled for January 28th (KHA to present). TC to review scope of concept design. KHA completed and presented study to TC during January workshop. Recommend adding 24" connector to existing culverts on Forest to assist with high demand discharge events and high-water conditions, as we have been seeing for several years. Further provided alternative road options, dirt and porous for considerations. Also provided recommendation to alleviate private lot drainage via property owners providing drainage easements to place a culvert system in to discharge their private lot drainage. March 4th: March 10th presentation to TC on recommendation for improvements to First Avenue and Forest Street drainage improvements. David Hansen mentioned the OC has a project the Town may wish to explore relative to establishing swales or berms on both Town and Residential properties with appropriate landscaping. TM and David to coordinate with Councilmember Andert for more info and see if we can incorporate in the Butler, Bessie and Forest projects. KHA will prepare three IPOs for March Town Council agenda. KHA to review survey files previously provided by MG. KHA to include septic drain fields in project survey. Schedule kick-off meeting – TC approved one CIP – upgrade and include equalizer pipes and swale details. IPO expanded to include topographic survey in private property. Rain event monitored by KHA. First field visit conducted as well as kick-off meeting. KHA completed field visits and prepared drainage maps to prepare conceptual construction plans. PEC Surveying and Mapping conducting survey work. KHA to present to TC in July (tentative). Rain events to be continued to be monitored. Meeting to property owners before TC meeting. MG to coordinate with HC on modeling of W. Second Avenue as part of the First Avenue and Forest Drainage Improvements. Schedule kick-off meeting – TC approved one CIP – upgrade and include equalizer pipes and swale details. IPO expanded to include topographic survey in private property. Rain event monitored by KHA. First field visit conducted as well as kick-off meeting. Drainage analysis and conceptual design underway. Coordination with MG on W. 2nd Avenue. Meetings to be scheduled with residents upon completion of the conceptual. Concept and approach to tentatively presented in two (2) weeks. VG conducted review and will provide TM with update after storm observation. Workshop on 9/22. Concept plan to be completed this week and submitted to the Town for review next week. HC to utilize same typical section as 7th and Butler. Redundant outfall pipe and swales to be presented by KH as part of workshop with TC. KHA to complete plans by December 2020. Zoom meeting to be conducted with residents. MG to send ICPR model to VG. 12/7/20 – 90-percent plans to be submitted in two weeks and to the SFWMD for permit modification. CS asked if a workshop is warranted. 1/6/21 90% Plans submitted, met with John F in field and he had some comments. We implemented and will resubmit this week. John F to meet with residents to discuss before KH finalizes plans. 2/1/21 KH will send full set and separate plan view to John F. Once we have reviewed full plans, we will create Zoom meeting with residents and in person when possible. 3/1/21 TC reviewing documents. JF reviewed and will discuss with HC on any comments prior to bidding. Public outreach to be conducted pursuant to JF comments. 5/3/21 Final plans completed. JF to discuss plan design with residents. HC ready to prepare bid documents. HC to send MG model modifications for proposed plans. TM to evaluate

availability of money for project. Zoom calls with residents pending. 6/7/21 Bid package is wrapped up by HC and submitted to TEM. 7/12/21 Bid package completed. Awaiting on gas line information to verify location. Package to be sent to TM and JF for review. Look at September approval and TC agenda. 8/9/21 KHA received all gas information. Plans updated and sent to TEM. Non-mandatory pre-construction meeting to be scheduled once advertised for bid. 9/13 Bids are due 9/22. 10/4 contractor selection will be on 10/12 Town Council meeting. 12/6/21 Contractor NTP provided. KH and Town staff are currently reviewing shop drawings. Looking at January-April construction time frame. 1/10/22 Pre-con meeting Friday. Contractor mobilizing next week. Tonya to work on notifying residents. 2/14 construction ongoing. Tony and John and Victor met out in field. Construction should be completed in a few weeks. Swales regraded to lessen slope. 3/7/22 Construction completed. Walk thru scheduled with TEM and JF. Change order approved for additional aggregate. Contractor to roll edges to level with adjacent sodding. 4/4 Project completed and Town monitoring improvement performance. 5.2 Discussions with Gray-Robinson regarding potential resident litigation regarding drainage flow through 1st Avenue swale and into Wauseon Bay. Further discussion pending. TM to reach out to resident and conduct walk thru 6/6 TEM discussed adding weep holes – VG proposed lowering boxes. KHA evaluated alternatives to address resident concerns. TD to set up meeting with resident once all alternatives evaluated. 7/11 Ongoing. 8/1 – Staff will be meeting with OC EPD this week and meeting with resident is TBD. 9/12 Internally met with team regarding options to potentially submit to Jeff and his attorney. Meeting to be scheduled TBD. 12/5 – No new updates. Waiting to hear back from property owner. **1/09 - No new updates. Still waiting to hear back from property owner.**

4. RR ROW (Sidewalks, Multi Modal Path, RR ROW): Town Council approved the purchase of the Ward/DP Lynn interests in the Railroad ROW. Once acquired the Town would be able to use the property for various projects: multi modal, stormwater, and landscaping) This would also allow for possible property swaps with those that own the RR Row so the TOW would have a continuous corridor from 12th/chase to Windermere Rd. 10/18 November 1st advertising period. TM working on negotiations for property swap. Conceptual design will commence once the property agreement is finalized. SB is coordinating with the Rubio's on property donation adjacent to Lake Down-Lake Butler canal. Still waiting on Wards. Awaiting on closing on property swap with the Town. Expect closing in April. Next agenda for resolution to vacate 20' on Dirt Main and provide it for the property owner (Ward). TM negotiating with property owner adjacent to Lake Down canal. The closing is next week. TM providing information to closing agent. Workshop held Monday night. TC approved property swap. TM to talk to residents on Lake Butler Boulevard for swap/purchase of RR property. SB still talking to Rubio's, updating TM on status. TM looking for funding sources for project (FRDAP, etc.). Rubio's agreed to donate land pursuant to conditions to be addressed by the Town. To be on July TC meeting. TM sent documents to Sorenson. SB to discuss contract with Rubio's. Heather to draft agreement for Rubio's. TM – after property acquisition, review multi-modal concept plan with Wade-Trim or KHA. SB working on funding opportunities to design project. To be named Windermere-Ward trail (prototype name – provisional). SB still negotiating with Rubio's – language in agreement for disclosure statement. Gray-Robinson to prepare agreement language for the Rubio's to approve. Memorial plaque to be provided as part of the agreement. No change. SB continuing to coordinate with the Rubio's regarding donation of railroad right-of-way property. Sorenson property in closing stage. Anticipated completion by December 2019. Scott spoke Rubio and will continue to coordinate with Rubio for their review and signature. TM to work with both KH and Wade Trim on survey, concepts and design from North to Park Ave. Rubio property donation completed. Phase I will be from Park Avenue to North Avenue. Funding to be applied through the MPO TAC. KHA working on scope for Concept Design. TM received scope and under review for approval at January TC meeting. KHA moving forward with the concept design phase. Project added to OC tax increase project list for possible funding source as part of a regional trail. 2/3 IPO approved at January TC meeting. Windermere WD looking to help fund portion

of the project. LRP needs to select stake-holder to represent at coordination meeting with various boards. TM to schedule first stakeholder meeting in February. Meeting occurred in February. Direction was given to KHA on look and feel of walk way. KHA and SB have a site visit scheduled in March. After the field visit, KHA will prepare draft concept for TC workshop. MW presented preliminary alignment for multi-modal path and concept plan for typical sections. The alignment is a curvilinear alignment with a 10-foot width and an elevated section along the top of the existing berm. Discussion regarding public meeting – pending on when a public meeting can be held. KHA to amend plans to remove elevated path. TC workshop to be scheduled by SB/HC. Present to LRP/TB in July prior to TC meeting workshop in the end of July for conceptual approval. IPO to be prepared for final design upon approval by TC of conceptual plan. TM to secure some initial funding for the project (without pedestrian bridge). Information to be ready by 6/12 for TB meeting on 6/18. Review plan with LRP on 6/25. Property on 10th Avenue, alignment to be adjusted. TM discussed with LRP and TB to be submitted to TC for conceptual approval of plan at next TC meeting. Coordination with Ocoee, MW provided multi-modal information. Once concept is approved, TM to take to West Orange for funding opportunities (connection to West Orange Trail). TM to request IPO from Mike Woodward, KHA. Work with TB regarding tree selection. Work with residents on type of vegetation to be planted. Include separate Add-Alternative for bridge. Need probable cost for pedestrian bridge. IPO for pedestrian bridge was approved to KHA. CS discussed KHA third party vendor for provider of pedestrian bridge. KHA will serve as liaison for bridge design. Vendors will present options to KHA and the Town for selection of preferred bridge structure. TM and MW working with West Orange Alliance on funding for the project. Pedestrian bridge is separate IPO. Provide multi-modal links. April 2021 funding to be considered by WOA. Meeting regarding pedestrian bridge scheduled for tomorrow. 12/7/20 – TM and MW has been working with West Orange County Health Care alliance regarding interconnectivity and connection between Windermere and Ocoee. NW got closing documents from Gray-Robinson for TM to review and approve. 1/6/21 RW conveyance has been completed. Robert to confirm with Gray Robinson. 2/1/21 RS met with West Orange Health Alliance, they are working on it and will present to board in April. State appropriations also asked for trail. Plans also went to Chamber of Commerce. TM also to reach out to additional private RR ROW owners in the near future. 3/1/21 TC working with MW on concept. Metroplan has large PDE projects and project is unlikely to be funded through this mechanism. Best bet for funding is WO Health Alliance. TM meeting with residents along route for possible interest in property acquisition (1st Ave and North). 4/1/21 Submitted to MetroPlan for funding. Set up meeting with West Orange Health Alliance for funding. Property at Second and Dirt Main to be purchased from resident (preliminarily agreed on). Heather Ramos, Gray-Robinson, to prepare agreement. 5/3/21 TM still working on acquiring remaining 4 parcels. Contracts in draft form. TM has two weeks to close deal to move forward with road design. TM updated that Fed \$\$ may be available for pathway. 6/7/21 TM has meeting with Singers June 9th. Title searches being conducted on all properties to be acquired for accurate offer and dimensions of taking. TM to have a meeting with West Health Care Alliance this week. July TC may need eminent domain resolution. 7/12/21 TC met with Health Care Alliance. Presentation slated for Health Care District (Ocoee, Winter Garden and Orange County). Discussion on prioritization and distribution of funding. August TC meeting – imminent domain taking powers to the TM. Survey in for Ward Trail. Schedule a walk thru with TEM and JF; and KHA (MW and HC). 8/9 Awaiting from funding from West Health Care Alliance and Feds. Focus on interactivity of trail. Property acquisition to be through imminent domain process (4 of 5 acquired). 9/13 – Massy's requested to exclude hold harmless. TM to meet with Hart. Singers want to close after October 1st. Still awaiting responses from Denoyles. TM to reach out to Denoyles again. 10/4 – Harts have signed on. Masseys have updated contact. Working with Singers. Denoyles still waiting for response. We are having neighborhood meeting this month. 12/6/21 Neighborhood meeting has been completed. Gray Robinson still working on closing for 4/5 lots. TM also working with Rose property and King Property for property swaps (10th Ave) 12/16 Public Information Workshop on Ward Tail. West Orange Healthcare Alliance monies to assist in

funding. 1/10/22 Ward Trail, working with Arborist. KH to look at saving trees by minor realignments or protection measures. KH to develop landscape plans for public meeting and then Town Council. February 17th meeting for government task force for funding prioritization. 2/14/22 Property swap meeting has been rescheduled due to weather. MW looking to adjust trail alignment based on arborist recommendations. TM has West Orange Alliance meeting on 2/17 3/7 Property swap scheduled for Thursday. MW had walk through and will revise plan as needed. West Orange Alliance has committed money for the project – will be prioritized based on jurisdiction. No funding from State anticipated. 4/4 – Town working with residents on South Main adjacent to Ward property (King and Rose). Securing ROW. HC said plans are done for a portion of the project, awaiting on property swaps. Still working on Denoiles property. 5/2 Acquired property on north between 1st and North Drive per TM. Massey property closing soon. TM working and negotiating on 8th and Dirt Main property. TEM working with Tree Board on landscape concepts. 6/6 TM indicated additional property swaps pending (112 West 8th Avenue & 824 Main St.). TM meeting with Singers and Denoiles this week and next for purchases. 7/11 90% plans presentation 7/11. TC in August. 4 Property swaps on TC agenda for Tuesday night meeting. 8/1 – 90% plans for Ward Trail will be on August TC agenda. Town has closed on Massey Property. 11/7 no updates to date. 12/5 – Steering Committee looking to fund projects but not until 2025. Working with FDOT D5 for LAP certification and funding. Scheduled for Fiscal Year 2023/24 (July 2023). 1/09 - FDOT to send Town training list for Fiscal Year 2024 (begin July 2023) LAP Certification.

5. W. Second Ave Roadway and Drainage Improvements: Town Council approved the widening and stormwater projects for West Second Ave. Staff met with public and have a conceptual design. Staff waiting on Orange County LMS response for funding before design can be brought back to residents and TC for Approval. 10/18. No change. Awaiting Notice of Funding from FEMA/DEM from Hurricane Irma. MG to address comments from DEM (Douglas Galvin) regarding project costs. MG addressed with Douglas Galvan. MG to coordinate with Douglas Galvan, DEM, on project status. No Change. MG e-mailed Douglas Galvan – no response to date. Applications under technical review – fiscal review complete. Continue to fill in edge of pavement. None. MG addressed RFI's from DEM Environmental Reviewer regarding project limits (project limits in latitude/longitude format). No change. MG to request status of HMGP application review. Still waiting on LMS contract. TM to coordinate design approval and workshops. TM executed Phase I agreement and sent back to DEM for approval and authorization to proceed. Total authorization is \$79,400 (75% Federal, 25% local share). Awaiting on executed contract with DEM for authorization for Notice to Proceed. Need easement and title search to be conducted to verify existing rights-of-way/easements. Also, more public hearings to be scheduled. 2/3 Coordinate with Gray-Robinson on title search for “right-of-way” for stormwater outfall to Wauseon Bay/Lake Butler. TM – pave Old Main from 2nd Avenue to Canal (IPO by KHA). TM emailed GR. MG submitted 4th Quarter report to FDEM in compliance with the executed contract conditions. Next quarterly report to be submitted by April 15, 2020. MG to coordinate with Gray-Robinson regarding title search for existing right-of-way bisecting West Second Avenue for stormwater management outfall to Lake Butler/Wauseon Bay. MG to coordinate with Diane Edwards on reserving Town Hall for 2 public forums (east of Pine Street/west of Pine Street). MG to coordinate with Wade-Trim regarding the existing 2” water main on West Second Avenue for upgrading per the water master plan. RS and MG to also meet with cul-se-sac owners regarding the Town taking over the cul-de-sac if agreed on with owners, including the securing of outfall easement to Lake Butler/Wauseon Bay. Title search by Gray-Robinson revealed that no rights-of-ways or drainage easements exist where originally mapped by the Orange County Property Appraiser. Their maps were updated to reflect no right-of-way or drainage easements. A public forum is to be scheduled (pending on pandemic lockdown) to solicit drainage easement(s) from residents. Mike Galura will coordinate with Scott Brown, Hao Chou and John Fitzgibbon on PRELIMINARY drainage design. TM to schedule a Town Hall Meeting for specific residents regarding the outfall easements at the middle of the project and at the end of the project (cul-de-sac). June may

be the tentative month for a face-to-face public forum. MG to re-print presentation boards for public forum. MG to also coordinate with WT on relocation and re-construction of existing water main as part of roadway improvements. MG to have updated presentation boards prepared for public forum. 2nd quarter report due first week in July. MG to coordinate with SB, JF and HC on design plans and calculations. Three meetings: 1) East of Pine Street residents; 2) West of Pine Street residents; 3) Cul-De-Sac residents. MG conducted video conference call with SB and KHA (HC, VG) to discuss peer review comments by KHA. MG to amend plans accordingly. MG to coordinate with WT regarding water main design to be incorporated with the plans. SB and WT coordinating with OCU regarding the water main design. Tentative August 5th meeting with OCU. Quarterly report submitted to Doug Galvan by TM. MG prepared and submitted Reimbursement Request No. 2 to Doug Galvan. MG continuing to revise plans per KHA peer review and prepare boards for public forum(s). MG to submit revised computer models to Victor Gallo, KHA. Schedule to have 90% plans completed by September. TM and MG to conduct Zoom meeting with residents on public forum. Three (3) virtual public workshops conducted (East of Pine Street; west of Pine Street; cul-de-sac). Minor comments received that MG will incorporate into the final plans. Expecting more comments. Comments and discussions include avoiding large trees, locations of speed humps, stop signs (at Pine Street), lane widths, curb type etc. Continue public forums with stakeholders on discussions of project design. MG working on quarterly report and time extension request. MG to review side street extensions pursuant to Zoom meeting inquiry by resident(s). MG to only look at double stack on side streets instead of extending Forest Street. MG discussed water main improvements with Mike Demko, Wade-Trim. What was proposed in the Master Water Plan report is to replace 6" water main west of Pine Street to 8". 4" water main to terminus would remain the same size. 8" water main size between Main Street and Pine Street would remain the same. No additional fire hydrants proposed on 2nd Avenue pursuant to Master Water Plan. 1/6/21 Mike G will provide update. 2/1/21 MG working on reimbursement #3. Plans sent to Christina Crosby at OCU. RS to reach out to Gray Robinson on 4 property owners at cul-de-sac. 3/1/21 Awaiting PEC on drawing of legal description on Lot 21 from Gray-Robinson title search. HC to send MG copy of OC agreement for the Park Avenue improvements. TM to schedule final round of public input on project. 4/1/21 Conducted additional Public Involvement meetings with Town Residents. Spoke with cul-de-sac residents and will move forward to establish a 20-foot wide right-of-way and Cul-De-Sac radius based new alignment (avoid existing large tree). Upon completion, a legal description and sketches will be prepared and agreements prepared by Heather Ramos, Gray-Robinson. Linear Park R/W purchased for property at 2nd Avenue and Dirt Main. Revise roadway alignment to avoid existing large tree at northwest quadrant. MG and HC to coordinate on final roadway alignment. TM to discuss project with Ms. McCarthy (Andrew McCarthy's grandmother) to get concurrence on design. 5/3/21 Gray Robinson and third-party attorney working on agreement with the residents at end of West Second Ave. Should have ready for June meeting. 6/7/21 MG reconfigured the roadway alignment to closely match the existing pavement. The project will be strictly a drainage project with the pavement to be reconstructed to the same dimension. JF and TEM to meet with the residents to get concurrence before preparing the right-of-way agreement (third party). 30% Water Main Improvement plans submitted to Christina Crosby (Orange County Utilities Division). 7/21/21 JF had last meeting on cul-de-sac, get concurrence in writing. MG awaiting concurrence from all residents prior to having PEC prepare legal description and sketches to accompany easement agreement to transfer road right-of-way to Town. MG to check on status of 30% water main plan review from Orange County Utilities (Christina Crosby). MG to coordinate with HC at intersection of West Second Avenue and Dirt Main on intersection configuration. 8/9 MG met with JF on alignment. MG to revise right-of-way alignment pursuant to field review and discussions. JF to coordinate with HR on draft agreement. Awaiting concurrence with Andrew McCarthy's grandmother. Received initial comments on water main plans from County (Christina Crosby). OC wants plans on 11x17 plan set format (currently on 24x36 plan set format). Meeting with Ed Torres (OC Utilities Division) scheduled later in month. 9/13 – Right-of-way limits for Aladar Replat cul-de-sac finalized between MG, JF and TEM. ROW

and temporary construction limits (TCE) submitted to PEC for preparation of legal description and associated sketches. Expect completion by end of week or early next week. Reimbursement request for design fees submitted to Doug Galvan (Reimbursement request No. 3 for invoices through period ending 5/31/2021). 10/4 – Waiting on PEC for final legal & sketch. Robert and John to meet with property owner. KH provided 60% OCU submittal peer review comments. 12/6/21 Michael Galura to provide update. Public Workshop moved until 12/13/21. 1/10/22 Requested and received HMGP grant extension. Submitted 90% plans to Town staff. On TC agenda for 1/11. Then will submit for SFWMD permit. Still waiting on some residents to sign easement agreement. . 2/14/22 SFWMD ERP Application submitted 2/1/22. Proceeding with modifications to Orange County Utilities water main plans (KHA peer review). Preparing reimbursement request to be submitted to FDEM. 3/7 MG issued Response to Comments to SFWMD for ERP. RS and JF working on easement agreements – MG will need for FDEM deliverables. MG to discuss extension with FDEM due to delay from SFWMD review. 4/4/22 MG submitted the Phase I deliverables (less the SFWMD ERP and the FDEP NPR, both which are pending) to Lourdes Vargas on 3/30/22. Mike is working on the quarterly report and reimbursement request. MG to review the OCU peer review comments from KHA and incorporate into 60% submittal to OC. 5/2 MG addressed FDEM comments and submitted per FDEM timeline. Addressed building replacement value issue per OCPA website. TM submitted potable water design to ARPA. JF to send easement agreements to MG. 6/6 MG addressed additional comments from Ed Warren, FDEM. Ed indicated that his engineering review is complete and that he has determined a BCR of 1.3 for the project, indicating that it is eligible for the FEMA funds under Hurricane Irma. He said that additional comments may come from other departments but engineering is complete with their review. MG also submitted the reimbursement request #4 to Lourdes Vargas, FDEM, for review. Lourdes had comments to remove any costs associated with administering the Phase I contract (quarterly reporting, reimbursement requests, etc.). These cost are to be removed from subsequent reimbursement requests. 7/11 MG provided responses to Environmental RFI from Amanda Chin, FDEM. MG also received request from Amanda Chin for a DRAFT of the Public Notice to be published by the Town for the Phase II funding of the project by FEMA. Any public objections during Public Noticing will need to be addressed before funding contract can be issued. POP extension requested to 10/31/22 and submitted (per recommendation by Lourdes Vargas, FDEM) to allow time to address current and future RAI's. 8/1 – Updated POP extension for FDEM review period. Extended to October 2022. Waiting to hear back from FDEM on draft public notice. Reviewing WM plans for consistency with recently approved MUP. Public Notice revised and sent to TEM per Amanda Chinn, FDEM. Public Notice to be published per approved FDEM methods of delivery. MG to provide electronic and hard copy of 100% plans to the Town for observation. Public notice to be published in Orlando Sentinel. 10/10 MG to update plans and submit to TM. Awaiting if any objections to Public Notice (30-day appeal period) has been filed. Any objections to be documented and addressed satisfactorily per FDEM. Provide FDEM with affidavit regarding publication of Public Notice in newspaper of general circulation. 11/6 Awaiting on status of Public Notice (any filed objections). Updating plans, quantities and specifications. 12/5 – Submitted to FDEP information requested for No Permit Required Letter. Public Notice completed with no public comment. **1/09 - Waiting on No Permit Required Letter from FDEP and Period of Performance Extension Date for HMGP Grant.**

6. Signage: TOW looking for consistent signage within Town. Part of Branding Revitalization. Street signs have been installed along major roadways. Now focusing on interior signage to make sure they are correct type, meet specs and are justified and enforceable. 10/18: SB to look into Parking Directional Signage when 5th/Forest is complete. Town Entrance Signage placed on hold. SB to look at parking directional signage. Parking directional sign ordered by SB. SB to meet with contractor on parking signs and public parking signs. Keep 10-ton weight limit for bridge over canal. SB to order sign for 10-ton limit. Parking signs are expected to be received this week. New speed limit signs installed by SB. Look at installing DO NOT BLOCK INTERSECTION signs at

intersections. SB to look to add in next round of regulatory signs. Most signs have been maintained by PW. Some signs may need to be replaced due to age. SB to monitor. SB awaiting quotes for flashing beacons. DO NOT BLOCK INTERSECTION signage to be included in next FY budget. Re-visit event signage – coordinate with LRP. No change – Advanced warning “Stop Ahead” beacons have been ordered and will be installed at approach to Windermere Road on Maguire Road. Beacons on hold due to backorder at manufacturer. PW to continue to maintain sidewalks. Posts were received but were damaged and were return. LRP tabled entry and event signage for next meeting. Footers laid for the 2 beacons. Start upgrading regulatory signs. Main and First pedestrian signage – LRP to prioritize. LRP prioritized First and Main. New signs and decorative posts have been ordered to replace existing from Parkridge Gotha to downtown. New signs and decorative signs completed. Upgraded all regulatory signs from Parkridge-Gotha to downtown. Working on first reading for Ordinance for right-turn only and fine amounts for violations. Radar trailer purchased by PW (can be used for educational purposes). New and regulatory signs have been completed. 2/3 Take pictures of new pedestrian cross-walks and post on Town website (Windermere Rd and Main). Order signage for southeast quadrant. New no right-turn signs at six locations and speed humps have been installed on Ridgewood. CS suggested that flags be temporarily placed on new signs, a temporary info board from PD could be used, and to put down traffic counters. SB will get with PD on these items. KHA to look at providing past traffic counts. There was a discussion on how to get this information reported to Waze and Google Maps. LRP made recommendation for RFW w/sign company to design, construct and operate Town Facilities event and gateway signs. PD monitoring, will get count when traffic patterns return to normalcy. Hold off on internal signs. Park Avenue signs to be updated. CS to set up LRP meeting – schedule workshop in August-September. SB put signs on bridge. Park Avenue signage ready to go (SB spoke with contractor). Resolve issue with property owner and WT on signage. SB and CS discussed with LRP and they need more information on scope of work. SB should have some notes to CS sometime this week to get a signage company onboard regarding the Town’s brand (beyond regulatory and traffic signage). SB reached out to OCPS for design processes. Looking at capabilities of companies currently contracted with the TOW for design. LRP will make final recommendations to TC. Individual IPO’s for signage discussed. Documentation to be sent to TM for TC agenda. To be done under KHA master services agreement. To be presented as an LRP item. Upgrade 6th Avenue. CS to send summary to LRP. Upgrade 6th Avenue. 12/7/20 – CS to send summary to LRP. Upgrades to be completed this week. TM to coordinate with Duke Energy. 1/6/21 Poles getting replaced with new upgrades on 6th Avenue. 2/1/21 Poles on 6th Avenue completed. John F and Travis have been doing maintenance on all signs. TC approved signage as part of KH master services. 3/1/21 Change guideline on font use to match the Town Facility. 4/1/21 Tonya will check on expenditures for signage for the year. 5/3/21: \$\$ Spent for this FY. Tonya creating signage maintenance plan within road maintenance plan. Will create CIP for remaining areas of Town to create consistent signage. 6/7/21 PW for signage will be budgeted for next FY with exception to emergency signage (alcohol-related signage) and NO RIGHT TURN per TEM. 7/12/21 NO RIGHT TURN signs have been installed. NO MOTORIZED VEHICLES signage to be installed at Lake Down. TC workshop in August to discuss Fernwood transition from a public park to a private boat ramp (Town Residents only). Issues are enforcement of parking at various locations. 8/9 TM to discuss action items with TC. 9/13 – NO PARKING on the weekend signs. To be deferred until ordinance has been approved by TC, 10/4 – Robert working on ordinance. 12/6/21 Robert and Tonya to provide update. Once Fernwood Comp Plan approved, Fernwood would then become boat ramp. Still waiting on Department of Economic Opportunity input. Changes to gate and fencing as well on hold pending DEO review. Once parking ordinance is approved in December, additional signage with ordinance numbers can go up as well. 1/10/22 Staff is reviewing sign language and gate types and operating systems. 2/14 PD, PW and TM met and will be moving gate and installing card reader at Fernwood Park. Will take to TC in March. Also reworking signage to match new ordinances. PW to look at Manors signage 3/7 TEM working on signage 4/4 TEM working on signage for the parks – Alcohol language for all parks. 5/2 TM issued

purchase orders for Manors and Marina Bay. Additional signage for Lake Street Park approved – purchase order approved. 6/6 TEM – new signage installed at Fernwood Park and other parks. TEM to work with PD for NO PARKING WEEKEND signs. Signage for Manors and Marina Bay ordered. TEM send MW options on Oakdale road closures for concurrence. 7/11 Oakdale to be discussed in TC meeting. Manors and Marina Bay signage being erected. 8/1 – Signage getting redone and will get installed. . 11/7 Cross-walks painted per TEM. JF to check on street lighting in front of Town Admin. 12/5 – Currently fixing street lighting in front of Town admin. No other updates. 1/09 - No new updates.

7. New Facility: Awaiting preliminary DD budget numbers from HJ High. Coordination with MW regarding impact to roundabout from new facility construction. JF to coordinate with ADG for modifications and scope on 6th Ave including ingress-egress to the library. This was not part of the original budget and will be priced separately for Robert to determine budget parameters. Maintenance Bldg. will be priced separately since it was not included in the original scope. The arborist was On site Friday May 2nd to perform air spading the trees that are to remain. The report will indicate tree root pruning plans. Determination was made that no special foundations will be required based on proposed building foundations and existing tree root extent. JF working on AIA102 form for GMP for review in July with HJ High. Early demo and foundation packages plan to be submitted in August for pricing and contracting. Demo tentatively to be completed 8/1. Meetings this week with design teams. JF to send current design schedule to Robert for TC. JF/ADG to present update to TC by 7/28 (workshop). Any TC directions can be approved at August meeting. Two workshops to be conducted per TM. Transition into construction document phase. Anticipate having demo package by mid- to latter part of August. Preliminary construction meeting to be conducted before demolition. Provisions for ventilation requirements for COVID-19 to be considered as part of budget increase. Received 50% CD set from ADG Thursday of last week. JF and Stephen Withers to prepare redlines and schedule meeting with ADG to further discuss. ADG working on 50% CD budget. Bidding abatement out. Abatement will be done as Change Order to. Waiting review comments from HJH. TM – request waivers for demo contractors (hold Town harmless). JF coordinate with demo contractor on turning off power. CS – coordinate on salvaging of materials from Town offices to be demolished and documented. 60% CD's complete; 90% CD's expected September 30, 2020. Demo package out to bid with HJH. Demolition to begin mid- to late October 2020. Coordination with all utilities continuing for disconnection. Gas has been disconnected as well as all Spectrum Business services. FDLE Server waiting to be relocated. Once server is relocated, power will be cut off and removed from old facilities. Coordinating salvage of old material from building with Tom Strupe and George Poelker from the Historic Preservation Board. Doing final selection with Demo contractor. Selection based on low qualified bidder. Abatement completed. Air quality test conducted in existing facilities. Pre-construction meeting with demo contractor TBD. 100% CD's expected by end of week. Looking into perimeter fencing prior to demolition. Demolition complete. Awaiting permit from OC Public Health for existing septic system. Kerosene tank removed. In for permit for permit fees for WT. Full GNP numbers from contractor pending. Minor items pending per JF. Ground breaking anticipated in approximately 3-weeks (possibly after Thanksgiving). Expect NTP in December with 10-12-month construction timeline. 11/2/20 Demolition complete. Awaiting permit from OC Public Health for existing septic system. Kerosene tank removed. In for permit for permit fees for WT. Full GNP numbers from contractor pending. Minor items pending per JF. Ground breaking anticipated in approximately 3-weeks (possibly after Thanksgiving). 6/6 JF doing final closeout to determine final payment by end of June. Waiting on final waivers and lien releases with prime contractor and sub-contractors

12/7/20 – JF had meeting with site contractor. Hope to have GNP soon. JF to coordinate with Computer Business, Spectrum and contractor regarding all infrastructure to be installed. Construction timeline is expected to be the same – to be discussed with contractor. 1/6/21 Working on finalizing all GMP contracts paperwork. JF to review changes with Guy Haggard to finalize all forms. 2/1/21 Fully executed contract approved by TC. Contractor is proceeding with submittals. 3/1/21 Work progressing. Foundation poured. Underground utilities relocated. JF working with Town Staff on purchases. Schedule for TC walk-through. TM to review Duke Energy easement agreement. 4/1/21 Budget review pending. Concrete block walls going up. Awaiting inspection at 6' height. 4/22 structural steel expected. Underground work is completed. 5/21 Duke to establish transformer. Stormwater/drainage tie-ins to be conducted. Water lines upsized pursuant to OCU. Meeting on 5/5/21 Tonya will update TC on progress at 5/11 TC meeting 6/7/21 Finalize cut sheets this week. JF to work with TEM regarding furnishings and fixtures for Public works. PW to be dried-in this week and Admin later this month. Electrical rough-in's on going. Meeting with LAG regarding connection to new Town facility. Steel structure for workshop not expected to be received until August. Should not affect schedule and CO for admin building. Currently on time and on budget. 7/12/21 On schedule. FF&E has been ordered. JF to provide monthly updates to TC. 8/9 Facility work on budget and on schedule per JF. Awaiting proposal from Stephanie (Spectrum) for IT services. TM and selection committee to select IT vendor for Town Facility. 9/13 – Signed easement agreement with OCU. Entered into agreement with Spectrum. 10/4 – John provided ppt of monthly update and will provide to TC. Tracking on schedule and temporary CO at end of year. Move in February. 12/6/21 Robert and Tonya to provide update. Issues with front doors arrival. Dealing with OCU issues relative to chlorination testing. Still on time and on budget, IT equipment to be installed this week and next. 1/10/22 Move is still anticipated for the first of February. John F. to coordinate FDLE move and comm design. Staff to coordinate grand opening and walking tours. 2/14/22 – Staff has moved into new facility. Punch list essentially completed. All exterior signage to be installed this week. Building to be pressure washed and cleaning – week after Spring Break expected for ribbon cutting ceremonies. 3/7 Roofing issues being resolved. Project under budget. Lightning protection repairs being installed. JF working on punch list towards final close-out. JF to reconcile on ODP. 4/4 – Grand opening 4/7/22 – 5:00 pm for opening. Punch list items being addressed. JF working with PD on accreditation – CCTV, card readers, etc. 95% closed out to the GC. 5/2 JF finalizing ODP changes – minor punch list items to be addressed (expected this week). Final walk with roofing contractor – address minor issues. 7/11 Address minor flooding in back parking lot. Awaiting final waivers. 8/1 – 100% closed out, final paid. Waiting on final releases from subcontractors for main building. Swept analysis completed for turning movement. 9/12 JF to meet with HJH on doors. Dedication plaque pending (Steven Withers has final design). Review latest version and finalize for approval by TM. 10/10 Minor punch list to be addressed by JF. 11/7 JF suggested final walk-thru with regards to warranties. 12/5 – mid to Late January for walk-thru punch list. **1/09 - No new updates, finishing punch list items.**

8. Fernwood Park Improvements: \$50,000 Awarded for Fernwood Park improvements. 10/18 SB working on RFP for Park Improvements for Fernwood. Project will match IDG approved plans. All contracts have been signed and waiting work from Andy Easton. All contracts signed. SB getting surveys done for site. Have not received Notice to Proceed. Awaiting boundary survey which is required per FRDAP. All commitment documents submitted to FDEP. Title search kicked back by FDRP (prepared by Gray-Robinson). Awaiting Notice to Proceed from FDEP. Notice of Commencement received from FDEP. 5-year CIP list to be built (SB to coordinate). TM requested items to be put on March/April TC agenda. Got Notice of Commencement. Come up with priority list for capital projects. PR to have a CIP list for SB. Central and Fernwood to be priority for FRDAP. SB has received cost estimates for drinking water fountains and butterfly garden. Dock quotes to be solicited by SB. Shoreline clearing will be in next FY budget. SB awaiting prices to remove invasive species from vendors. Dobson has removed invasive species in upland

areas. Trees will also need to be removed. Aquatics company will continue to treat vegetation in waters. FWC and Orange County EPD permits have been amended. Invasive species being removed. Boardwalk concept pending based on removal of additional vegetation along projected alignment. SB stated approximate ETA for design is 6-months. Took down some large invasive trees. SB met with PR on footprint for trail and walkway. Obligation for boat ramp repair. Deadline to complete in 14 months under FRDAP conditions. Contractor is developing draft footprint and estimated cost for the boardwalk. Contractor provided SB with quote for the design, engineering and permitting of elevated nature walk. Nature trail in design phase by Contractor. Final concept drawings completed. Moving into construction plans and scope of work. 2/3 Final concept prepared including elevated nature trail. Sent to PR for review. Concept in design. FRDAP schedule through April 2021. TM and David Hansen to coordinate on driveway within the park. Partnership with OC, FWC and TOW. Need to stabilize the driveway and launch area. David Hansen to help guide Town through OC permitting and variances. Video conference with SFWMD – will require a permit for the boardwalk. Meeting with Orange County EPD – 2 permits required including tree survey and wetland delineation. Draft concept prepared, beginning preparation of construction plans. 4-6-months estimated for design. FRDAP grant deadline April 2021. 5K run has been postponed, but not canceled. SB working with OC EPD on wetland delineation. Surveyors are picking up wetland flagging. Also virtually met with SFWMD on permit submittal. FRDAP forms sent to TM for execution. TM coordinating with FDEP regarding parking configuration. SB said that the SFWMD is requesting an individual permit for the boardwalk due to encroachments to Sovereign submerged lands. FRDAP grant application withdrawn. Meeting tonight at 5:00 pm to discuss. Town to conduct a charette for presentation (to be conducted on Zoom). Coordinate with Councilman McKinley on P&R input. No changes. Getting charettes and scheduled for the residents. TM to discuss with Councilman McKinley on opening of Lake Street Park. TM to as PR to complete and close-out. PR to determine what to do with boardwalk. 11/2/20 PR to determine what to do with boardwalk. 12/7/20 – Pending. 1/6/21 On hold until we get RFQ completed. Travis M. to contact companies and get quotes for dock fix. 2/1/21 JF to get three numbers from separate vendors for dock fix. JF to look into dock inspections checklist and schedule. 3/1/21 TM needs third quote for dock fix pursuant to Town procurement procedures. JF and TrM will review and recommend quote. 3/12/21 TM approved dock replacement. Waiting on schedule from vendor. Once there is a time frame scheduled, TM will post. 4/5/21 Await dock replacement until Butler design completed. TrM spoke with Peter Fleck regarding the dock. No permit required since it is a maintenance activity on existing dock. 5/3/21: Dock fixed. Remaining improvements to be determined at time of Butler Basin design completion. Tonya looking into cameras at dock. 6/7/21 Looking to install security cameras. 7/12/21 Boardwalk to be dealt with after the 100-perent plans for Butler Basin. P&R recommends transitioning park into boat ramp only. TM to work with TC to set up workshop. 8/9 Boat ramp conversion will provide the Town more enforcement powers. TEM awaiting quotes for fencing and gates. Going with wrought iron for structural stability and will not affect stormwater design. 9/13 – Redesignated to boat ramp in October. Continue working with OCEPD if Town can get no wake zone or no motorized water craft at Lake Street and Lake Down. 10/4 – Working with EPD on no wake and on Lake Street and Lake Down Park. 12/6/21 Waiting on Comp plan amendment. Robert to touch base with Orange County EPD on Bird Island Ordinance. 1/10/22 Robert to work with Tonya on signage and gate systems. First reading of comp plan amendment on 1/11 TC meeting and second reading in February. 2/14 PD, PW and TM met and will be moving gate and installing card reader at Fernwood Park. Will take to TC in March. 3/7 Plan on TC agenda. 4/4 Fencing slated for fall 2022. 5/2 All fencing and appurtenances ordered per TEM. Additional request for signage. 6/6 TEM – supplier indicated gates to be received by July. By August anticipate everything to be installed. 7/11 August slated for park improvements. 8/1 – Electric installation will be this week/next week and fence installation in the next couple of weeks. 9/12 Fencing completed, Gate post completed. Issuance of keys for locked gate pending (TEM coordinating). 10/10 Gate locking system to be installed (pending). 11/7 TEM to get with installer regarding access. Fence was fixed due to tree

falling. 12/5 – Gate system installed and waiting on instructions from installer. **1/09 - Contractor needs one more USB drop and it is in progress.**

9. **Cross Walk Improvements:** W&D has funded two cross walk improvements. First one on Second/Main and the next on 6th/Magnolia. 10/18 Two additional locations – 6th Avenue east of Ridgewood, and Main Street near Estancia. Funded one cross-walk. Location to be determined. Consideration for cross-walk locations: 1) 6th Avenue near Ridgewood Drive; 2) Main Street near Estancia. LRP to make recommendation and present to TC for approval. LRP has reviewed and approved Johnson Park crossing (east of Ridgewood), to be presented to TC for approval. More usage and higher volume of traffic. Cross-walk improvements completed. Look at an additional cross-walk based on availability of funding. LRP made 2 recommendations – 1) Estancia; 2) First Avenue and Main Street. Retrofit existing cross-walks. LRP recommendations made. Awaiting funding. No change. Waiting on Windermere W&D funds. No change. No Change. Awaiting on Windermere Wine & Dine. Crosswalk on Windermere Road and Main should be completed soon. 2/3 Windermere W&D agreed to fund new cross-walk at 1st Avenue and Main Street. On TC agenda for 2/11. Windermere Road and Maguire Road has been completed. TC approved RRFB at Main Street and 1st Ave. Footers have been poured. Awaiting deliveries for RRFB's. RRFB's completed at Main Street and 1st Avenue and operational. Nothing additional. Waiting on W&D. W&D to conduct event in March 2021 for sponsorships. TM to meet with HPB. 12/7/20 - W&D to conduct event in March 2021. 1/6/21 No update. 2/1/21 Ongoing. 3/1/21 - Ongoing. Another tier of cross-walk locations to be reviewed. LRP to have updates. 4/5/21 Taking to LRP. 5/3/21 No LRP in April so taking up in May. 6/7/21 Cross-walks will be discussed at TC meeting. Will be part of proposed share agreement. 7/12/21 Still waiting on monies and property share agreement with the 500 block. 8/9 Considering postponing event due to Covid. Decision to be made in October. 9/13 – Windermere Wine & Dine moved to February 2022. Business as usual in late September. Food truck event to be held in September. 10/4 – Wine and Dine event in February 2022. 12/6/21 Priority of crosswalks established. TM to provide list from LRP: 1. Estancia 2.WRC. 3 9/Main. 1/10/22 LRP made suggestions and Town staff has priorities. 2/14 – Working on grant for additional crosswalk. TM to talk to WW&D regarding funding for crosswalk. JF working on park bench additions by WW&D. TM working with W&D on funding. JF working with W&D on benches, 5/2 TM working with W&D and get on TC agenda. 6/6 TEM got quotes on all cross-walks (average \$20,000 apiece). TM to coordinate with WWD on funds and present to TC in June 7/11 TEM sent purchase order to contractor – delays in receiving materials. 8/1 – Ordered and waiting for install. 9/12 Awaiting cross-walk assembly. 10/10 TEM to provide update. 11/7 Cross-walks being installed this week. 12/5 – Crosswalk has been installed. **1/09 - No new updates. Crosswalk down by Estancia on Maguire Blvd will be next.**

10. **1887 Schoolhouse:** HPB and Tree Board have worked on the planning and implementation of repairing and improving the grounds and structures. Currently HPB is looking at making sure the building is sound prior to making additional improvements. SB sent out various requests for contractors and engineers to look at to no avail. In addition, SB was able to get a vendor to take care of the grove area to make sure it is well maintained and healthy. 10/18. Approved to replace citrus trees that have died and contract with maintenance firm. HPB to make decision on structure analysis. Working with Amanda Black on search for architect. HPB still searching for tree/grove maintenance. Architectural evaluation approved by TC. Based on architectural evaluation, HPB will generate a CIP. Architectural evaluation awaiting. The architect has conducted initial condition of schoolhouse. Architect to return to review the condition of the schoolhouse. Architect has returned several times to continue to evaluate. Architect sent in plans to Town for review. SB to be liaison for Eagle Scout project. HPB working with architect and on future CIP. HPB creating scope of work based on architect's evaluation. HPB still having open discussions regarding the architect concept. HPB meets 1/8/20. HPB discussing options for materials to

use and style of final look. 2/3 HPB still having discussions. To keep status on National Historic Register, HPB will need to maintain the same architectural look. HPB had conference call with SHPPO about signage and marker. No changes. TM to meet with potential volunteers for community hours. No changes. 12/7/20 HPB met and agreed to remove sidewalk around schoolhouse facility due to drainage issues. TM to address this week. 1/6/21 Completed. 2/1/21 Siding boards are currently being repaired. 3/1/21 Sidewalk removed and disturbed areas re-sodded. JF met with local Boy Scout troop who have an Eagle Scout project to connect the school house to the privy. 4/5/21 HPB is meeting this week. Eagle Scout project completed. 5/3/21 HPB guidance needed on how they are proceeding. 7/12/21 Batten boards for the siding are completed. Eagle scout painting boards. 8/9 TEM advised to work with her and JF on Boy Scouts understanding of the site when doing the improvements. 9/13 – TEM to get quote to clean up wilderness around school house, removal of well and landscaping. Orange County is in process to decommission well, 10/4 – Working on decommission well ongoing. 12/6/21 Orange County Permit to decommission well anticipated this week and work on it next week. 1/10/22 Met last week and selecting new chairperson. The well has been fully decommissioned. Patio is completed and pathway improvements are next. Looking at installing aesthetic “wishing well”. 2/14 - Ongoing 3/7: Ongoing. PW graded parking lot. Will seed the area. 4/4/22 Sod place in parking lot. Garden Club has been working around school. New board member – 5/2 New chair for Historic Preservation board. 6/6 no change. Change on leadership by that committee. 8/1 – No meetings in summer. Next meeting in October. 9/12 Meet on October. 10/10 No Change. Focus by board on 100th Anniversary. 11/7 No Board meeting in October. 12/5 – Minor debris cleanup. **1/09 - No new updates.**

11. Street Sweeping: Best Management Practice (BMP) under the stormwater NPDES program. 10/18 Ongoing. MG has article to send to TM, SB and JF. Ongoing. HC to consider street sweeping article for Gazette. No change. Ongoing. KH to prepare article in Winter Gazette about street sweeping. Due date is 11/22. MG to get street sweeping quantities from SB and determine TN (Total Nitrogen) and TP (Total Phosphorous) and submit the removals to DEP under their STAR program (State Annual Report). HC to provide MG with quantities. MG to submit as part of STAR to the FDEP doe pollutant load reduction reporting. 2/3 MG received quantities from HC. Will combine with NPDES section. Ongoing. SB and KHA submitted street sweeping volumes to FDEP. KHA and USA Services documenting quantities. Continuing to document. Quantities are continuing to be documented. Still documenting on monthly basis. Ongoing. 12/7/20 – Ongoing. 1/6/21 Coming out once a month. Travis to get paperwork and send to Hao. 2/1/21 Ongoing on obtaining reports. 3/1/21 Ongoing with reporting. 4/5/21 Ongoing. 5/3/21 Tonya and Hao to work with vendor on quantities to report for NPDES compliance 6/7/21 Reporting scheduled for every 3rd Wednesday for every Month per TEM. 7/12/21 Ongoing. TEM to put together schedule for street sweeping and vacuuming (3rd Wednesday of each month) 8/9 TEM has set up regular schedule. 9/13 – Street sweeping to commence every 3rd Wednesday of the month. TEM to get latest report from vendor. 10/4 – Ongoing and documenting for NPDES Annual Report. 12/6/21 Ongoing and NPDES Annual Report submitted. 1/10/22 Ongoing and providing information to KH for next NPDES Annual report in two years. They are coming at scheduled times. Need to include in STAR report. 2/14 – Ongoing, services being provided on schedule and data sent to KH. 3/7 Ongoing. 4/4/22 Street sweeping ongoing. 5/2 Ongoing. 6/6 TEM – provide HC with street sweeping quantities. 7/11 Ongoing. 8/1- Ongoing and documenting. 9/12 Street sweeping last week. 10/10 Ongoing and documenting. Post-storm documentation to be sent to KHA. 11/7 Ongoing. TEM sent documentation to HC. 12/5 – Ongoing. **1/09 - Ongoing.**

12. Vacuum-Truck Services – Cleaning of stormwater structures and storm pipes. Bid awarded by Town to Waste Services Group at January TC meeting. Started on 8th and Bessie Street to Magnolia. Log of linear footage of pipe cleaning and volume of debris collected. Completed in 1-1/2 days. Scheduled for 12th Avenue and Oakdale Street

stormwater project. MG to provide SB with copy of recorded drainage easements for the storm sewer system in the back of the homes. Next project is west 8th and Forest Street. Plan is to initially clean the entire system with a future target of bi-annual cleaning of systems. SB to receive cleaning logs from WSG for documentation for NPDES measurable goals. Provide measurable goals for NPDES reporting. Done with cleaning 12th and Oakdale Street. Moving next to west 8th Avenue drainage system for cleaning. TM to coordinate with SB on availability of funding for continuing work. Working on funding. Continuing the cleaning of stormwater/drainage structures. Plan to conduct bi-annually. SB to provide budget amount to TM. Completed west 8th Avenue and currently working on Lake Street. Targeting North Oakdale (north of 1st Avenue). Completed North Oakdale including First Avenue stormwater pond. Next is Johnson Park pond then Ridgewood ponds. Completed. SB will continue working with vacuum trucks for other projects. Completed main drainage basins. Biannual treatment of all infrastructure and also CCTV of infrastructure. Structures will also be GPS's for inventory. SB to draft release on dewatering so there is no confusion as to what is being placed in stormwater ponds. Will also get costs on transport. 2/3 Completed cleaning of all stormwater systems, including Main street and its associated detention chambers. Crews returning this week to begin return cleaning off the dirt roads, as well as to start GPS and CCTV all systems to record current conditions and control points moving forward with an overall inventory of the Town's stormwater system. Will combine with NPDES section. 12th Street and Oakdale vacuum, GPS and CCTV services have been completed. 12th and Oakdale completed. Videoing process. SB working with KHA on GIS for inventory. GIS being prepared for drainage infrastructure mapping. Continuing GIS mapping of Town's MS4 system. Completed west 8th Avenue – working towards First and Forest. Ongoing. Set up for Bi-yearly cleaning. Continuing GIS mapping. Ongoing. Videoing for GIS mapping. Conducting videoing for GIS mapping. TM to present costs for upkeep for Street Sweeping and Vacuum-Truck services. Ongoing. 11/2/20 Conducting videoing for GIS mapping. TM to present costs for upkeep for Street sweeping and vacuum truck services. 12/7/20 - Johnson Park used as discharge location. HC tracking invoicing and debris removal for NPDES reporting (coordinate with TrM). 1/6/21 Ongoing. 2/1/21 Current reports received; HC will continue to track. JF and TM to request per service invoicing. 3/1/21 Ongoing. 4/5/21 Ongoing. 6/7/21 TEM and HC have been working with the street sweeping vendor on structure inventory. 7/12/21 Ongoing. TEM to put together schedule for street sweeping and vacuuming (3rd Wednesday of each month). Solids to be transported offsite. TEM waiting on quote for cleaning of all storm drains. 8/9 TEM to reconsider vacuum-truck vendor services (current vendor un-responsive). 9/13 – Ongoing. Lake management consultant to help coordinate when they come onboard. 10/4 – Ongoing and documenting for NPDES Annual Report. 12/6/21 Ongoing and NPDES Annual Report submitted. Tonya is looking at some options for contracts with other companies for this work. 1/10/22 Tonya met with Shenandoah and they will provide quote for vacuum services. Atlantic pipe has already sent Tonya a quote. Tonya to establish baseline of how often structures need to be cleaned. Need to include in STAR report. 2/14 – New vendor will be contracted with this week. 3/7 Horizon Land Management is new vendor. TEM to send agreements over for execution. 4/4/22 – MG provided TEM with data, completion of missing structures and pipes to be cleaned. 5/2 TEM met with vendor. Ongoing 6/6 TEM discussed difficulty for cleaning structures due to duration when they were last cleaned. 7/11 Ongoing. 8/1 – Ongoing and documenting. Spreadsheet created for schedule and documentation. 9/12 Vendor completed tracking sheet which was forwarded to HC. 10/10 Ongoing and documenting. Post-storm documentation to be sent to KHA. 11/7 Ongoing. TEM sent documentation to HC. 12/5 – Ongoing. **1/09 - Ongoing and will provide vacuum quantities.**

13. Lakefront Maintenance: TOW to control invasive species along lakefront that is under Town jurisdiction. 10/18: Awaiting Orange County for permits. Once received, invasive plants to be removed by selected contractor. Awaiting Orange County permits. To start in January. Received OC permits. All permits now received. Start herbicide spraying. Pond by Windermere Elementary also maintained. Aquatic Systems has been onsite for a

couple of months. SB coordinating with David Hansen, Orange County Environmental Protection Division, regarding limits of herbicide application. Information on cleaning Town's social media pages. Ongoing. Monthly treatment (15 locations). Vegetation cleared at Windermere Rec Center pond. Ongoing. SB to assess Windermere Rec Center pond on water recovery – check lake levels for comparison. Spraying is on a monthly basis on lakeshore and in the parks. Continuing on monthly basis. On Lake Down, 5 cypress trees planted and sent documentation to OCEPD to close out the complaint. Ongoing. SB received quotes to clean up the lakeshore (vegetation removal and tree removal). Continue to construct elevated boardwalk for nature trail. 2/3 DH discussed possibly funding “backyard BMP’s” (swales, rain gardens, planting, etc.). Ongoing. SB to provide TM with budget numbers. Continuing. Continuing. Ongoing. SB to address wax myrtle growth by Lake Bessie boat ramp. Land alteration permit would be required. Ongoing. TrM to check with vendor (Solitude Lake Management) on cycle of lakefront maintenance. Check on maintenance plan and frequency. 1/6/21 Travis M reached out to vendor to get scheduling. Will follow up again to establish a set schedule. 2/1/21 JF and TM working on permit and is in process of resubmitting. 3/1/21 Received Lake Crescent permit. TrM working on schedule. 4/5/21 Ongoing. 5/3/21 Tonya and Hao to work with vendor on quantities to report for NPDES compliance. Will also TV and GIS lines and structures. All will be cleaned out prior to Storm Season. 6/7/21 Town is using Solitude as their vendor and they have been providing reports to TEM. Considering a lakefront maintenance consultant to assist with planning for lake-front and swale maintenance to keep constant tabs of tasks and maintenance schedule. 7/12/21 Ongoing. RFP going out on 7/23/21. 8/9 RFP committee met last week. Got additional information from respondent (JF to meet with TD to discuss and make recommendation for awarding of bid). 9/13 – Lake management consultant RFP to be included in TC agenda for approval. 10/4 – Aquastem will have onboard meeting this week with Staff. 12/6/21 Amy is working with Solitude Lake Management. Will do a State of the Lakes at January TC meeting. 1/10/22 State of Lakes report at TC 1/11 meeting. Things we need to work on and things that are going well. 2/14 Lakes Consultant is good with services being provided by Solitude. Consultant will review 50 ft setback 3/7 On going. Lake consultant provided WT with letter per TEM. 4/4/22 Setbacks relative to pool – workshop with TC (Brad Cornelius of WT to conduct workshop) to evaluate what the Town will adopt. 5/2 WT doing presentation to TC for pool setback. DRB recommend not to amend. 6/6 BC discussing with Winter Park on pool setbacks (to eventually be presented to TC). 7/11 Ongoing. Taking ordinance to DRB in near future. 8/1 – Town looking at new vendor and add swale maintenance treatment. Lakefront impact Ordinance Amendment will go to DRB 8/16. TC on 9/13. 9/12 TC in October and November. 10/10 – TEM waiting on proposal. 11/7 TEM – new vendor (AWC) coming onboard. 12/5 – Aquatic Weed Control just finished first treatment and working with Lakes Consultant. **1/09 - Ongoing and providing documentation for review.**

14. Town Hall: PW to inventory entire Town hall for improvements and repairs. 10/18: TM asking for long term needs of Town Hall – full assessment (i.e., lighting, kitchen, audio-video, etc.). SB contacted Landmark Construction for proposal. SB spoke with Landmark for numbers for quote. SB to contact Landmark Construction. SB talking to other contractors regarding quotes. SB requested proposal from Edmundson. SB has meeting with general contractor to give him some prices. Ongoing for quotes. Need all fixed assets identified and provided to NW (for insurance purposes). W&D to consider helping with Town Hall fix. No Change. TM needs to complete inventory. W&D want to invest in Town Hall including: roof; kitchen; etc. Working on pricing with contractor over the next 60 days. W&D has interest in TH improvements. SB has requested scope of work and cost from HB & Associates for TH improvements. SB to meet with CPWG to do a complete evaluation of Town Hall (both interior and exterior), subsurface to roof including electrical, HVAC, sound and lighting, foundations, etc. 2/3 Met twice with cpwg as well as their co-consultant MLD Architects. MLD has an extensive history with historic buildings and are familiar with the State Historic Preservation Office (SHIPO) requirements aka Secretary of Interior. Some opportunities for grants may be possible for the historic portions of the

work. SB met CPWG to provide a cost to evaluate Town Hall. MLB architects to also provide review of historical elements of Town Hall. SB to look at mid-end of March for scope of work. Will need RFQ. Contractor just send SB scope of work and cost. SB is reviewing. On Hold. SB and JF to get together on AC so TM can submit for the CARES act. JF to conduct thermal scans for various buildings. New toilets, automatic soap dispensers and automatic faucets to be implemented. Scheduled AC replacement for week after next (week of November 16th, 2020). 12/7/20 - AC replacement at Town Hall completed per TrM. Awaiting on final invoice and maintenance plan and warranty. 1/6/21 UV lights are installed and inspected. Look at getting roofer out to look at rotted area in the flat roof section. TM and JF to look at temporary fixes. 2/1/21 Minimal maintenance until after Town facilities completed, then will do full repairs. Temporary fixes to roof and porch steps. 3/1/21 Temporary fix on roof completed. Permanent roof replacement is pending. TrM gathering quotes for fixes from roofing vendors. 4/5/21 TrM getting quotes on roofing from prospective vendors. Bids to be presented to TC for consideration. 5/3/21 TC to approve roof fix on 5/11 6/7/21 Budget increased for Town Hall. Inventory required for Town Hall elements. Next FY targeted to implement improvements. The flat roof did get repaired per TEM. 7/12/21 FY 21-22 funding for full assessment of Town Hall (April-May of 2022 for assessment). Continue cosmetic repairs till full assessment. 8/9 Ongoing. 9/13 – Ongoing. Minor fixes and cleanup continuing. 10/4 – Ramp fixes have been completed. Continuing to monitor and making minor repairs. 12/6/21 Wait for after new facilities are completed and then do an assessment. 1/10/22 Ongoing. 2/14 – AC/heater was previously serviced but Tonya will look into if there is an issue. 3/7 – TEM has new vendor to check AC – coordinate with TM. Look to doing assessment over the summer if funds allow. 4/4/22 Assessment over the summer. 5/2 TEM RFQ for assessment. 6/6 TEM – Draft document completed and RFQ pending. 7/11 RFP submitted – Councilman Williams will be on selection. 8/1 – Received one proposal. Committee will reject proposal and will look at doing study under \$35K and will coordinate with Price architect. 9/12 TEM reached out to Price Architects to help with Town Hall improvements. TEM to receive quotes. 10/10 – JF had meeting with historical architect for proposals. 11/7 – TEM to review proposals. 12/5 – Three quotes obtained and taking to TC on 12/13 to approve working with Mr. Price. **1/09 - Tonya to set up kickoff meeting.**

15. Water Utility Master Plan: TC approved master plan for water utilities for entire TOW. 10/18 – TM to issue RFQ for water master plan (entire Town). TM spoke with Wade-Trim on structure of RFQ. WT to meet with Orange County Utilities (OCU) regarding what OCU will need for RFQ. RFQ to be issued today on Town Website and Demand Star. Wade-Trim, KHA and CPH are the three consultants short listed for study. SB, JF and MG to review their proposals and select consultant for study. Oral presentations conducted on 3/17/19 (Wade-Trim, KHA). Consultant selection pending. Selection of consultant will be on TC agenda for approval. SB to issue ranking of consultants. Scheduled for April TC meeting. Awarded to Wade-Trim at April 9th TC meeting. WT to schedule kick-off meeting (SB, JF, MG to attend). Tentative schedule of 12 months to complete study. TM to consider lobbyist (2020-2021 FY, approximately \$60,000 for lobbyist) to assist in securing funding for implementing plan. June Technical Advisory Committee (TAC) meeting for project. Awaiting follow up schedule from Wade-Trim. TAC meeting with Wade-Trim (meeting in July). Presentation at September TC meeting. Web conference call between WT, Town and OC Utilities to be scheduled by SB regarding the water utility master plan on September 19th. Additional workshop with TC on September 23rd to be conducted to provide update and information on project status. October 22nd TC workshop with Wade-Trim to provide status of project. Scheduled for completion in March 2020. Presentation was completed on 10/20. OCU to provide flow information. Scheduled completion in March 2020. Ongoing. Coordinating with Orange County Utilities. WT requesting meter readings on hydrants for more accurate data. WT to provide update on coordination with Orange County. Confirm some flows and reevaluate fire hydrants (Orange County). 2/3 Final flows and calculations have been completed. JF and SB meeting with WT to review drawings and design. Preliminary plans sent to Angie Brewer to review for possible funding sources. Goal

to have TAC meeting mid-March with outcome moving toward TC in April. TC workshop in March. Final TAC meeting on 3/10 at 2pm. Workshop pending. Monitoring infrastructure package to see if funding is available. MG to coordinate with SB on 2nd Avenue water main improvements (6") WT to provide status update to TC regarding water main improvements. Awaiting final report. Presentation by W-T at last TC meeting. MG to coordinate on W. 2nd Avenue. Discussion on funding opportunities. Follow up meeting with OCU to discuss plan. Discussion on funding and verification of low rates. MG to coordinate with Mike Demko, WT, regarding water main design along West Second Avenue. Finalized plan submitted to TC on 9/8/20. Looking for funding opportunities for all phases. MG to coordinate with WT on 2nd Avenue water main improvements. Look at funding sources. 12/7/20 – Implementing water main improvements through CIP projects. 1/6/21 Been adopted. 2/1/21 RS submitted to Orange County for appropriations. Actively incorporating plan into new projects. 3/1/21 Recommendation to be incorporated into all Town CIP's. 3/12/21 Still waiting on State Appropriations and will discuss with TC from American Rescue Plan \$\$\$ 4/5/21 awaiting on appropriations for funding of implementation of recommended improvements per approved Master Plan. 5/3/21 Appropriations not approved. Hao will work on scope and costs to possibly create MSBU for 1st Court. Appropriations were NOT approved. TM sent appropriations request to Federal Govt for consideration. Waiting on American Rescue Act \$\$\$ 7/12/21 New grant available – TM to see if Town can qualify. Awaiting on American Recoveries Act for funding. 8/9 Ongoing. 9/13 – OCU stated that MUP needs to be updated with additional information requested. On next TC agenda, Wade Trim contract to be amended to update MUP for OCU resubmittal and approval. 10/4 TC approved Wade Trim contract and John and Tonya will be meeting with them to kickoff. 12/6/21 Wade Trim finishing report and will submit to OCU. Tonya to check on status. 1/10/22 Wade Trim submitted to OCU yesterday. 2/14 – OCU provided RAI and Wade Trim has resubmitted to OCU. It is currently under review by OCU. 3/7 OCU still reviewing master plan. 4/4/22 WT prepared update and responded to RFI. HGL report provided by OCU. 5/2 Awaiting final approval from OCU (Wade Trim). TEM to reach out to Wade 6/6 WT to address additional comments from OCU. All water main improvements contingent on approval of MUP. 7/11 Approved by OCU. 8/1 – Review to confirm that projects under design are consistent with approved MUP. 9/12 Approved by OC for review fee. Inspection fees during construction. 10/10 – No change – been approved by Orange County Utilities. Project to be removed from list.

16. Cut-Through traffic: Town Council approved KHA to do study on cut thru traffic and determine where traffic originates. 10/18 Town Council Workshop on 10/30 Schedule follow-up meeting with KHA. KHA to conduct TC Workshop scheduled on 1/22/19. Includes evaluation of continuous right turn southbound from Main Street to Chase Road. Await recommendations. Presentation by KHA at February TC meeting Tuesday night. Work with OC on county level on Windermere Road/Main Street roundabout and Main Street northbound to Chase Road with exclusive right-turn lane to relieve traffic congestion. Brought to TC Tuesday night. Police to continue with 90-day study – compile data and further evaluate with KHA study. TM asked Brad Cornelius for an urban planning study – possibly RFQ. Workshop in May, included in budget analysis by TM. Workshop planned this month. CS – Update from PD. Number of travel counts received from KHA. Data evaluated and will be discussed again at July TC meeting. TM had meeting for ideas for cut-thru traffic. TM has meeting with County Administrator. To be discussed at September 23rd TC workshop. LRP took no action on cut-thru IPO's. Work on cut-thru traffic plan for Ridgewood Drive. LRP will look at Oakdale Street improvements. TM to schedule workshop for LRP recommendation for SE Quadrant. LRP made second recommendation for SE quadrant and Ridgewood Drive. No right turns on Ridgewood Drive and Lee Street (at certain times). LRP recommending to table the Ridgewood Drive one-way ordinance indefinitely and move forward with requesting revised traffic engineering study for time limitation no right-turn only on 6th Avenue at Ridgewood Drive and Lee Street. SE quadrant discussion at a later date depending on effectiveness of no-right turn signage at Ridgewood Drive and Lee Street. MW to review plan before 12/18 TC meeting. OC has requested projects

from the Town. 2/3 TM working with Winter Garden, Ocoee and Oakland: West Orange Transportation Alliance (WOTA). TM worked with staff and KHA and submitted projects list to Ocoee and will submit to OC on 2/4. TM meeting with OC Staff about 1 cent sales tax. WOTA to meet on Friday. TM to update TC on Feb 11. New no right turns signs at six locations and speed humps have been installed on Ridgewood. CS suggested that flags be temporarily placed on new signs, a temporary info board from PD could be used, and to put down traffic counters. SB will get with PD on these items. KHA to look at providing past traffic counts. There was a discussion on how to get this information reported to Waze and Google Maps. Monitor right-turn issues. TM asking OC on 6th Avenue and Chase Road round-about road improvements. Conversations ongoing. Ongoing. Ongoing. 12/7/20 – No change. 1/6/21 No change. 2/1/21 RS met with Commissioner Wilson and sent documentation for 12th and Chase and 6th and Main improvements. 3/1/21 TM to continue discussions with Commissioner Wilson regarding appropriations for the 12th and Chase and Main Street improvements. 3/12/21 Meeting was cancelled last minute (again). We will continue to advocate for relief. 4/5/21 Issue with Duke. TM discussed with residents. Re-evaluate when school starts back up in the fall to provide a more realistic scenario. 5/3/21 Tonya created speed bump request process similar to stop sign process (resident initiated). TM met with Forest St residents about Left Turn only sign out of 5th Ave parking lot. Left Turn only signs not budgeted by PD. TEM reached out to PD for their vendor and received quote of \$4,500 for portable signage. TM to review and consider. 7/12/21: PW, PD and JF working on several locations identified by residents. Need assessment, evaluation, then determinations as to what if any changes will be made (signage, etc.). 8/9 Ongoing. 9/13 – Ongoing. New portable speed detection sign boards currently on Ridgewood Drive. 10/4 – Ongoing. 12/6/21 Ongoing. 1 cent sales tax initiative to be discussed in mid-December and early January. 1/10/22 Portable speed detection sign moved to First and Forest. Robert had meeting with County on 1 cent tax initiative. Will move forward with initiative in November. Town of Windemere share could be at \$367k a year if passed. 2/14 – Town Staff is working on Oakdale. 1 month info ended on 2/11. TM to review stats with PW and PD. Schedule Public Workshop then to LRP then TC workshop 3/7 TM to review Oakdale data. Speeds within 85%. TM to schedule workshop to discuss with stakeholders. 4/4/22 TM preparing presentation to Oakdale residents for 4/13/22. 5/2 TM – 2 cut-thru traffic meeting with residents. Setting up meeting with LRP then Workshop with TC 6/6 Presentation on 6/14 regarding cut-thru traffic. Proposal is to close access points south of 6th Avenue and possibly 12th/Chase. 7/11 – To be discussed at TC. 8/1 – Strips, signs and flexible diverters are ready to be installed on 8/18. 9/12 Diverter in place. TEM addressed golf cart access. Positive compliments on diverter. 10/10 – Golf cart resolution for next TC agenda. Also 30-day appeal period pending. 11/7 Take to December TC meeting for review. 12/5 – Diverter is going to be discussed at 12/13 TC Meeting. Public meetings anticipated depending on TC direction. **1/09 - KH is working on proposal for diverter island and will include public workshops.**

17. Sidewalk improvements/repairs (maintenance budget) outside of multi-modal project: 10/18: TC at approved budget. PW to inventory sidewalks and prioritize for repairs. SB to inventory after first of the New Year. Await till February for inventory, work to be done after school is out for summer. No change. SB to inventory existing sidewalks, which will establish the funding needs to improve sidewalks. SB met with sidewalk contractor on project in front of Johnson Park. Contractor to begin sidewalk improvements on Summit and Highland. SB working on sidewalk list. Work in the Manors. Priorities to be established by next month. Sidewalk Repair Inventory prepared and completed by JF/SB. Based on sidewalks that need corrective action to be compliant with ADA. Survey presented in 8 sections with linear footage for each section for sidewalk repair/improvement. Planned for 2-year capital improvement plan. TM to update CIP based on JF inventory. Awaiting QES update on pavement management plan. SB – met with contractor. Manors will be first location to be addressed then Park Avenue. SB and JF to work on prioritization in developing a sidewalk CIP. CS requested a written CIP for each sidewalk improvement project in order to appraise citizens of project status. SB and JF

completed priority map. SB & JF to provide CIP with year and cost. SB has a CIP for review of projected costs over a 5-year period (CIP attached to these minutes). Currently working in the Manors with approximately 75% complete of root-damaged sidewalks and other sidewalks in disrepair (i.e., trip hazards, cracking, etc.). Contractor working at Manors on repairs, removing cracked panels and trip hazards. 2/3 Manors repairs completed, as well as portions on north side of Park Avenue between the Manors and Marquises Court. No new updates. Budgeted money spent for FY. Last project completed for Town Hall. TM needs second year estimated CIP costs of sidewalk improvements. Awaiting budget for sidewalk improvement for next fiscal year. Waiting on budget approval for next FY. 6th Avenue is priority project. Projects to be advertised for procurement of construction contracts. Portions of 6th Avenue replaced between Lee and Ridgewood due to fallen tree. 1/6/21 6th Avenue completed. Need to determine which area for repair is next. 2/1/21 Received proposal to extend construction on 6th Avenue from Highland to Ridgewood. 3/1/21 Sidewalk improvements on 6th Avenue to Ridgewood completed. 4/5/21 JF to coordinate with Tonya regarding implementation of various plans. TM to conduct budget review analysis. 5/3/21 Tonya to work with John on creating new CIP based on need and liability. Checking an area at Willows. 6/7/21 Virtual meeting to discuss sidewalk hazards. Looking to conduct pilot project for sidewalk maintenance company. 7/12/21: New company hired by Town will conduct an assessment of the Town sidewalks, prioritize improvement needs and prepare a CIP list for the Town to use for implementing sidewalk improvements. Vendor is 4-6 weeks out. Will start with 4 pilot projects. 8/9 New sidewalk company on board. TEM – 8/9 locations by Town Hall and Willows to be addressed. 9/13 – Work to be finalized this week in front of Tavistock office on 6th Avenue. 10/4 – Working on fixing trip hazards. 12/6/21 Tonya getting per square yard quotes based on sidewalk assessment from last year. 1/10/22 Tonya dealing with OC contractor for sidewalks and is waiting on bid. Anticipated February TC agenda. 2/14 – Sidewalk contractor approved by TC. 3/7 TM to send V3 conceptual sidewalk improvements by KHA (developer to construct sidewalk). 4/4/22 – Mayor received comments from residents. Replace first, then shave sidewalks to meet ADA compliancy. 5/2 TEM met with sidewalk contractor and walked problem areas. 1st week of June targeted to begin (contractor to coordinate with JF). 6/6 TEM – quote received and reassess sidewalk improvements with staff. 7/11 Ongoing. Repour sidewalk in front of Admin building. End of July – Start Park Avenue. 8/1 – Completed, vendor is Condor. 9/12 All sidewalk improvements completed for currently FY. 10/10 – TEM working with contractor on next phase of repairs. 11/7 Park Avenue completed, moving to 6th Avenue. 12/5 – Sidewalk repair at Park and then 6th Avenue. **1/09 - Sidewalk repair to continue on 6th Avenue and then Main and Chase.**

18. Bessie Street Stormwater Improvements: #2 priority on Stormwater improvements. Continuous maintenance issues and flooding. 10/18: MG to provide scopes. SB provide scopes to TM. On Hold. Awaiting HMGP application review. IPO to be presented at August TC. To be on August 27th special meeting agenda. TC provided direction to revise IPO scope for September 10th agenda. TM to review revised IPO from KHA. KH to contact OC representative responsible for lake water quality testing. KH to provide responses to IPO comments. Awaiting to complete responses to resident concerns by KHA. TM to review revised. 2/3 IPO revised as requested and moving forward. IPO has been approved. SB and KHA to have kickoff meeting in March. IPO approved by TC. Kickoff meeting conducted between SB and KHA. Design survey and geotechnical services underway. 4/22 field review by KHA. Surveyor to complete this week and move on to Butler Street. KHA received topographic survey. HC working with SB on typical sections. End of June, preliminary concepts to the Town (SB, TM, CS). HC to schedule meeting. Preliminary concept plans to be presented by KHA at scheduled meeting or review and approval before moving to final design. HC coordinating with SB on concept plan. HC to prepare quarterly report. Concept plan ready next week. Community outreach to be conducted in October. Utility proposal from KHA pending (per Master Water Plan). Include Add Alternatives per TM. 12/7/20 Zoom meeting conducted with stakeholders. JF to meet with homeowners regarding project design concept prepared by KHA. IPO to be presented to TC

for approval at December meeting. 1/6/21 RFQ due Monday, 1/11 at 5 pm. 2/1/21 Contract for design award with be on 2/9 TC agenda. 3/1/21 AIA agreements executed. Coordinate with Doug Galvan regarding time extension. Surveying on Bessie has been initiated (PEC). HC to review where additional swales and pipes are needed. Town to contact residents regarding surveying for project. 4/5/21 Survey to begin this week (Oakdale/8th and Magnolia Street). May delivery date expected for 45% plans. 3rd and Magnolia to be included as part of the project per DEM combination of projects. HC to provide separate IPO for water main improvements. 5/3/21 Survey Crews out later this week. Should have 45% plans by end of May. 6/7/21 Awaiting survey for project. HC working on 3rd and Magnolia. Workshops to be considered for both projects by end of June/early July. Public workshop followed by TC workshop after receipt of 45% plans. 7/12/21 Preliminary 45% plans and exhibits submitted to TEM and JF. Comments received and Kimley-Horn is updating for resubmittal this week. Public workshop is scheduled for 7/27. 8/9 45% plans on TC 8/10. VG-water main designs underway. 9/13 Pre-Application meeting with SFWMD scheduled for this month. 90% Plans to be prepared for submission for review in October. Water main schematic submitted to TEM for review (to be submitted to OCU). 10/4 – SFWMD submittal and OCU schematic submittal this month. KH working on final plans. 12/6/21 Public meeting completed. 90% plans completed. TC for approval on 12/14. Final plans by end of year. Respond to RAI this week. Water main plans submitted to OCU this week. 1/10/22 WMD permit received. KH working on draft bid package for submittal to Town and DEM. Water main plans to be resubmittal to OCU this week. 2/14 – Compiling documents for submittal to DEM this week. 3/7 Phase I DEM deliverables submitted for review. 4/4/22 - DDF tables submitted to DEM for review of BCA. 5/2 FDEM issued RAI's responses completed by KHA. TM submitted ARPA costs for potable water designs 6/6 FDEM asking for more data on DDF (Existing conditions). 7/11 – RAI responses submitted. Extension for POP to be submitted to cover RAI responses. 8/1 - POP Extension and all Phase 1 reimbursements submitted. Waiting to hear back from FDEM. 9/12 HC working with FDEM on BCA analysis. 10/10 BCA analysis completed and sent to FDEM for review. 11/7 HC remove scope of work that does not have direct benefit. Plans and cost-estimates to be updated and to be resubmitted to FDEM. HC to request POP extension from FDEM. 12/5 – Reduced scope of work sent to FDEM and currently under review to get BCA ratio to one. Pre-app scheduled with FDEP for No Permit Required Letter. **1/09 - Field meeting scheduled with FDEP and KH responding to No Permit Required Letter RAI from FDEP.**

19. Butler Street Stormwater Improvements: #3 Priority on Stormwater improvements: Continuous maintenance issues and flooding. 10/18: MG to provide scopes. SB provide scopes to TM. On Hold. Awaiting HMGP application review. IPO to be presented at August TC. To be on August 27th special meeting agenda. TC provided direction to revise IPO scope for September 10th agenda. TM to review revised IPO from KHA. KH to contact OC representative responsible for lake water quality testing. KH to provide responses to IPO comments. Awaiting to complete responses to resident concerns by KHA. Awaiting to complete responses to resident concerns by KHA. 2/3 IPO revised as requested and moving forward. IPO has been approved. SB and KHA to have kickoff meeting in March. IPO approved by TC. Kickoff meeting conducted between SB and KHA. Design survey and geotechnical services underway. Wetlands delineated in Fernwood Park. Design survey to be completed this week and field reviews by KHA forthcoming. KHA received topographic survey. HC working with SB on typical sections. End of June, preliminary concepts to the Town (SB, TM, CS). HC to schedule meeting. Preliminary concept plans to be presented by KHA at scheduled meeting or review and approval before moving to final design. MG to forward HC quarterly reports to be prepared by KHA for the project (HMGP Project # 4337-449-R), Project has been selected for HMGP funding under Hurricane Irma. Concept plan in final review by SB and TM. Concept plan done. Community virtual outreach on 9/16/20 at 6:00 pm. Utility proposal from KHA pending (per Master Water Plan). Include berms and other improvements in Fernwood Park. 12/7/20 - TM and HC met with homeowners. IPO to be presented to TC for approval at December meeting. 1/6/21 RFQ

due Monday, 1/11 at 5 pm. 2/1/21 Contract for design award with be on 2/9 TC agenda. 3/1/21 No additional surveying needed. HC moving to 45% plans. HC provided schedule regarding resident discussions on 45% plans. April-May for Butler; June-July for Bessie. On schedule for delivery 45% for this month, including Fernwood Park. May workshops likely for resident feedback. 5/3/21 KHA working on 45% plans. Once ready will present to TC, residents and LRP. 6/7/21 JF to have a meeting with Mr. Clark to clarify the project intent. TC to consider in July. 7/12/21 TC meeting to approve 45% plans at 7/13 TC meeting. Upon approval KHA will proceed with producing final plans and coordinating the water line permitting with Orange County. 9/13 Pre-Application meeting with SFWMD scheduled for this month. Plans to be prepared for submission for review. Submit water main schematic TEM for review (to be submitted to OCU). 10/4 - SFWMD submittal and OCU plans submittal this month. KH working on final plans. 12/6/21 Public meeting completed. 90% plans completed. TC for approval on 12/14. Final plans by end of year. General permit obtained. Water main plans submitted to OCU this week. 1/10/22 KH working on draft bid package for submittal to Town and DEM. Water main plans to be resubmittal to OCU this week. 2/14 – Compiling documents for submittal to DEM this week. 3/7 Phase I DEM deliverables submitted for review. 4/4/22 – DDF tables submitted to DEM. 5/2 FDEM issued RAI's responses completed by KHA. TM submitted ARPA funds for potable water design. 6/6 FDEM asking for more data on DDF (Existing conditions). 7/11 – RAI response submitted. Extension for POP being prepared and to be submitted. 8/1 - POP Extension and all Phase 1 reimbursements submitted. Waiting to hear back from FDEM. 9/12 HC working with FDEM on BCA analysis. Final calcs signed and sealed and submitted to FDEM. 10/10 BCA analysis completed and sent to FDEM for review. 11/7 Butler approved by FDEM. MG to provide HC with template for Public Notice language. 12/5 - Pre-app scheduled with FDEP for No Permit Required Letter. **1/09 - Field meeting scheduled with FDEP and KH responding to No Permit Required RAI from FDEP.**

20. Windermere Pavilion: – JF coordinating with DBC on site plan. Received two proposals for outdoor pavilion preliminary design (site plan and concept drawing). Presented to TC at April meeting. Meeting on Thursday. JF to follow up with Hunton-Brady. Review rough draft of rendering. Subcommittee revisions to concept plan provided by HB. Meeting scheduled for review on 9/11 at 10:00 am. Hunt-Brady to complete final plan and renderings. JF received updated version of renderings and will distribute to committee. JF awaiting on sketch of interpretation of drop-down roof version of rendering. Providing comments to H-B to complete final plan. One minor comment on the pavilion elevation, addressed by H-B. Expected cost to be between \$400K and \$500K. 2/3 To be run through LRP prior to TC meeting. TC/CS to provide direction moving forward. Received preliminary plans, TC wants to go through DRB and conduct a workshop. CS has been coordinating with BC at Wade-Trim for their review. JF to send information to CS. CS to schedule with TM to discuss pavilion status. Workshop to be scheduled for May 19th. JF sent package to CS. DRB approved preliminary plans. Next step is to present to TC in early August meeting (budget meeting). Discussion on funding options and opportunities. Concept approval. Awaiting funding opportunities from Rotary. Rotary trying to come up with funding plan. No changes. Rotary to have a plan. No change. 1/6/21 No change. 2/1/21 Ongoing. 3/1/21/ - On Hold. 4/5/21 On Hold (Town working on other CIP projects). 5/3/21 Funding Opportunity up for approval by TC on 5/11 6/7/21 TM spoke with attorneys and contract is to be approved (pending). 7/12/21: Agreement signed. RFP for Project Management Services should be completed by this Wednesday or Thursday. 8/9 TM awaiting comments. 9/13 – Rotary created their own RFQ (did not use Town's boilerplate). Rotary Received 5 respondents and conducted interviews. JF to be Town's independent reviewer. Rotary selected ZHA as PM for Windermere Pavilion. ZHA recommended for project management for pavilion for Rotary Club of Windermere, LLC. Recommendation to be on TC agenda for approval. 10/4 – RFQ response this Friday. 12/6/21 Robert working on bid process with Rotary. Need to contact Rotary Attorney and JF for status. 1/10/22 Look at using design-build AIA form. Town staff to review RFQ package. 2/14 – Town staff to respond to questions on RFQ package. 3/7 Selection committee to be created (including JF) to review

submitted responses to the RFQ. Only 2 respondents. Selection process pending. 4/4/22 Committee has made selection to design-build contractor to be presented to TC on 4/12. Asbestos inspection conducted and report expected next week – do not anticipate any issue. 5/2 Initial review of contract with contractor – no asbestos identified. JF recommended site plan for review by TC. 6/6 Surveyors are out to do a site survey for the pavilion site. Once survey is complete, a demolition plan will be prepared. JF will coordinate with Tree Board based on arborist report. 7/11 Received survey over weekend. Preparing site plan for pre-approval by TC. Once site plan is approved, demolition can proceed. 8/1 – John F is working on getting final budget and conceptual site plan to schedule workshop. Arborist report will be completed. 9/12 JF to meet regarding final design of pavilion. JF to coordinate with Andy before a formal TC workshop is scheduled. 10/10 JF to meet with ZHA regarding demolition permit. 11/7 JF to meet regarding the tagging of trees. To be included for December TC meeting. JF to meet with Hunton-Brady and prepare Executive Summary to TC. 12/5 – JF working with arborist and Tree Board. 45% design submittal to TC in January. **1/09 - January 23rd public information workshop scheduled.**

21. Dirt Main (Rose Property): Road water not flowing. Stormwater solutions pending (contingent on railroad right-of-way property swap). PW to address. Possible use of Town-owned property north of 10th Avenue for stormwater use. On-going. Ongoing. HC submitted proposal to TM and SB for improvements to Dirt Main. SB will work with HC to review possible drainage/road realignment design. HC, CG and SB met on site. Ideas on realigning dirt road. HC to provide scope and fee for engineering services to counter problems. Concerns by residents on stormwater runoff in the area. HC to send scope and fee to SB. Approval of scope – KHA defining drainage basin and preparing concept plan for maintenance work to realign Dirt Main which will address stormwater related issues. 12/7/20 KHA working through their miscellaneous services contract. HC to move forward with dirt road realignment and coordinate with JF regarding location of property corners. 1/6/21 KHA submitted and need to get with property owner. Met with John F in field. KHA to resubmit concept plan addressing John F comments this week. Get property corner surveyed. KHA to coordinate with Duke Energy on distribution pole relocation. 2/1/21 Final concept submitted, KH contacted Duke Energy and they will require 2-3 months for relocation. Bishman surveyed property corners. Arborist report obtained recommending removal of tree. KH to call Duke Energy to start relocation process. Likely to be done in house. 3/1/21 JF met with Tree Board, Enviro-Tree to remove tree. JF awaiting Duke on pole relocation. 4/5/21 HC and JF met with Molly Rose 4/2/21 to discuss options for improving drainage improvements. IPO to be prepared for the proposed drainage improvement including design survey. Relocation of Dirt Main design pending relocation of Duke power pole. Tree's trimmed and removed. 5/3/21 Design in progress 6/7/21 Survey underway. End of June/beginning July for 45% plans to JF and TEM. 7/12/21 KHA coordinating with Duke Energy to have existing power pole relocated in mid-August. Topo survey has been completed. Kimley-Horn is currently working on 45% plans design. Anticipated submittal next month. Survey completed. JF working with Duke to relocate power pole. All staff coordinating with property owner and Wade-Trim. Design in Progress. 8/9 Power pole to be relocated within next 2-weeks (Duke Energy). Once pole is relocated, road realignment can be conducted. Stormwater improvements will likely need to be RFP'd. KHA working on plans. 9/13 – KHA to submit % plans to TEM and JF for review. Duke Energy has relocated power pole. 10/4 – KH has completed plans and John and Tonya will meet with Rose property. 12/6/21 John met with property owner. Rose and King property may be open to property swap. KHA to hold until property swap is confirmed. 1/10/22 Waiting on Rose property and 1036 Main Street property swaps. KHA on hold for plans. Power pole relocation will 4/22 be completed and Town staff can temporarily realign road off of private property. 2/14 – On hold until property swaps have been confirmed. 3/7 On Hold until TM meets with Mr. King. Meeting is this week. 4/4/22 – On hold until property swaps are completed. 5/2 awaiting quotes and working with GR. 6/6 Finalizing documents on acquisitions. 7/11 KHA submitting revised IPO with additional

properties. 8/1 – IPO for design at additional properties will be on August TC agenda. 9/12 Topo surveying initiated per HC. 10/10 – Topographic survey completed. Road temporarily shifted. 11/7 HC-topographic survey completed, conducted field review with TEM. Roadway to be realigned and shifted to be within Town R/W. Plans to be prepared and submitted for review. 12/5 – Working on 45% plans for December/January submittal and workshop. 1/09 - 45% plans submitted to Town staff for review.

22. **Pavement Management Plan:** SB working with four (4) professional engineering companies to develop a scope of work and costing for the Town's PMP. The survey/study will evaluate the existing roadway system conditions and provide future recommendations for paving and longevity. SB received no response. Received proposal from QES on budget (\$60,000). On hold for this FY. RFQ slated for next FY (original PMP prepared by QES). SB working on RFQ – pending. SB working on RFQ – next FY. Selection committee to be determined. RFQ is out (TM, JF and Roger Gatlin on selection committee). 12/7/20 Two respondents on RFQ (QES and PDQ). JF, TM, and Roger Gatlin to be on selection committee). 1/6/21 Robert Smith to look at and discuss pushing out selection to possibly April. 2/1/21 Pushing out to fiscal year 2021/2022. 3/1/21 No change. 4/5/21 RFQ – 2 submittals been received. Move awarding of RFQ till next FY. 5/3/21 Will RFP next FY. Tonya and Councilman Davit to coordinate on drafting scope for RFP 6/7/21 JF to work on RFQ by October of this year. 7/12/21: In FY21/22 Budget. TM, PW, JF and TD to coordinate on drafting scope to advertise in RFP. 8/9 Plan on April FY21/22 for advertisement. 9/13 – On hold until April 2022. 10/4 – On hold until April 2022. 12/6/21 Tonya and staff to work on drafting RFP. 1/10/22 Town staff to review areas that need to be repaved. Tonya has reached out to contractors to see if they are willing to piggy back contract with other municipalities for this work. Town staff will coordinate with Councilman Davit on rehabilitation options. 2/14 – Town staff working with Middlesex. Waiting to get contract back from them. Councilman Davit and staff has reviewed. 3/7 Middlesex proposal on TC agenda (selective pavement repair). All Main Street/6th Avenue, partial Maguire Road. 4/4/22 – Middlesex contract approved. TD asked if the project could be done at night. 5/2 TEM working with PD and Middlesex on paving improvements. Looking at week of 6/5 for paving. 6/6 PMP to be held off till next FY. Middlesex conducting pavement improvements. 7/11 Starting night work on Main Street tonight. RFQ for PMP update scheduled for next FY. 8/1 – Middlesex completed their work. Pavement management Plan RFQ scheduled for September. 9/12 RFQ to be issued in new FY. RFQ to be drafted and reviewed between TEM and JF. 10/10 – JF reviewing proposal by QES. 11/7 On agenda for November 14th meeting. 12/5 – Approved by TC on 11/14. 1/09 - Kickoff meeting completed with QES and they are starting work.

23. **Downtown Brick Restoration Improvements** – 3/7 JF and TEM to reach out to brick vendors regarding brick pavement repair. JF and TEM to review repair typical section to determine the best solution. 4/4/22 Cathcart looked at the typical sections – JF had brick contractor looked and provide proposal – wait until after school lets out. 5/2: 6th and 4th Repaired this weekend. 6/6 TM indicated spot on 6th Avenue to be addressed. TEM to ask for quote to do the work. 7/11 TEM purchased order for 6th Avenue (between new Admin building and Town Hall). 8-1 Waiting for bricks to be prepared. Town staff is following up with World Class Stone and Tile. 9/12 TEM – section by Town Hall and new Admin building completed. 10/10 Look at other improvement areas. 11/7 area outside of administration building completed. 12/5 – Address tripping hazards and remove broken basketball pole. 1/09 - Tripping hazard and broken basketball pole has been addressed.

24. **Paving of Dirt Main** – IPO signed by TM. Survey scheduled this week. Survey completed. Horizontal and vertical alignment pending. Address large oak tree on northwest quadrant of 2nd and Dirt Main (MG and JF reviewing). 12/7/20 HC provided typical section and alignment. 1/6/21 Field meeting with John F conducted. KHA will address comments

and resubmit to John F and Robert Smith next week. 2/1/21 HC to finalize and send exhibits to JF and RS. 3/1/21 HC finalized road and drainage plan, including sidewalk tie-in. 4/5/21 MG to coordinate with HC on roadway alignment. Masee property has been preliminarily acquired (pending agreement). 5/3/21 TM has two weeks to get properties 6/7/21 HC awaiting on property acquisitions. 7/12/21: TM has commitment from 4 of 5 property owners. Will be working with GR and KHA on acquisition and design. HC moving forward with final design of pavement and ribbon curb alignment per acquisition of properties. HC to coordinate with MG at intersection of West Second Avenue. In FY 21/22 budget. TM, PW, JF and TD to coordinate on drafting scope to advertise in RFP. 8/9 JF and TEM walked site with HC and MW to review design. MW to coordinate with MG at intersection of Dirt Main and West Second Avenue. 9/13 - 40% plans to be submitted at end of month. KHA walked site with Town staff. Water main schematic to be submitted to TEM, JF and OCU later this month. 10/4 –Public Meeting on 10/18. 12/6/21 Public meeting completed. TC November meeting approved to go to 90% plans. KHA to complete for staff review by end of January. Water main plans submitted to OCU this week. 1/10/22 KH working on 90% roadway and water main plans. 2/14 – Water main plans submitted to OCU. Finalizing 90% design and will be ready for submittal this month for public meeting. 3/7 HC to provide TM cost for pavement from North Street to the canal. KHA submitted exemption from SFWMD – approval pending. 4/4/22 – HC received SFWMD exemption – HC to provide TM with revised costs. 5/2 KHA to finalize design. 6/6 HC – coordinating with MW on Ward Trail improvements. HC to submit 90% plans – TM to set up workshop. 7/11 On hold for funding (due to HMGP projects). HC to complete plans and set up workshops. 8/1 – Ready to schedule for workshops. 9/12 90% of plans on TC agenda. 10/10 – 90% plans approved by TC. KHA to proceed with 100% plans. 11/7 HC-90% plans approved, HC to sign and seal plans. Project to be constructed in the future. 12/5 – Final plans have been submitted. Shelved until funded for construction. **1/09 - No new updates.**

25. Pedestrian Bridge – IPO approved by TC 9/8/20. Survey underway. Elevations to be established. Meeting scheduled week of 11/2/2020. First Zoom meeting to be held 12/7/20. 1/6/21 KH sent Town survey results. Workshop in January with Town Council to decide on type of bridge and colors. Then we can move forward with design. 2/1/21 TC selected Bridge Brothers Bowstring 14-foot width, KH working on getting color palates and height. Will be on February TC. RS asked for appropriation from state. 3/1/21 Proceeding with final design (KHA). Target Healthcare Alliance meeting in April to have concept plan. 4/5/21 KHA (Mike Woodward) completing design. 5/3/21 Waiting on completed design 6/7/21 Surveys to be completed by this month per MW. 7/12/21: Surveying complete. Walk thru to be scheduled next week. 8/9 MW coordinate with bridge designers. MW to get a tentative construction schedule to TEM. 9/13 - MW send conceptual plans to TM for review. Town selected Option #2. Town provided feedback on abutments – electing a shorter bridge with concrete walls and decorative fascia at the edges of the canal. KHA will provide 60% plans by the end of the week for Town review and walk-through by Town selected arborist. Meeting this month with SFWMD to confirm permit status needs. Bridge design by manufacturer is underway. Construction schedule (after NTP to contractor) is estimated to be 6-months. 10/4 – Eric to provide arborist evaluation and then public meeting will be scheduled. 12/6/21 KH submitted for SFWMD permits. Received trail permit. KH Resubmitted RAI for bridge portion. 1/10/22 WMD permit received. Incorporated with overall trail design. 2/14 – Potential realignments to avoid trees and will submit this week. TM to meet with West Orange Alliance 2/17 3/7 MW to discuss with TM on public meeting. MW to revise plan. 4/4/22 – MW discussed that the project will be done with the Ward Trail project. 5/2 KHA 90% plans in 2 weeks per MW. Possibly June TC for approval. 6/6 90% plans submitted. TM to schedule workshop. 7/11 MW coordinating with FDOT on funding. Plans to be discussed tonight at workshop. 8/1 – 90% TC on August 9th. 9/12 90% plans approved. MW coordinating with FDOT District 5. 10/10 – 90% plans approved by TC. TM coordinating with FDOT on federal funding. MW indicated TB walk-thru pending. 11/7 Town to be LAP certified – MW working with FDOT on certification. DRMP to be used by Town for CEI services. TM and TEM to work on educational element of certification

process. 12/5 – Working with FDOT D5 on LAP funding and certification. **1/09 – KH is addressing comments from FDOT and working on required certifications.**

26. TM to budget for wastewater report through infrastructure funding (IPO by KHA). Identify types of projects most eligible and pre-requisites. 8/1 – Town Staff will look at funding opportunities with Orange County. 9/12 On hold. 10/10 No change. 11/7 No change. 12/5 – No change. **1/09 - No change.**

27. Lake Street Park – move to privatize park. TM to discuss with Commissioner Wilson and OCEPD (Liz Johnson) on swimming zones and watercraft exclusion areas. FRDAP grants would need to be returned (TEM to review). 8/1 – Will go back to TC on August 9th. Potential returning of FRDAP grant and fence installation with keypad. 9/12 Meeting this afternoon. TEM reached out to FDEP regarding FRDAP. 10/10 Update to be provided by TEM in November to TC. 11/7 Updated to done in December. 12/5 – Presentation in January. **1/09 - Town staff to coordinate with OCEPD.**

28. Low level lighting at 5th and Forest – Town staff looking into it.

29. Stormwater Master Plan – Project has been kicked off. MG is coordinating with surveyor and Town staff for inventory.

Acronyms

ADG: Architect Design Group

BC: Brad Cornelius (Wade-Trim)

CIP: Capital Improvement Project

CE: Code Enforcement

CS: Chris Sapp, Town Councilman (previous liaison)

CP: Claudia Purser, Florida DEM

DAC: Direct Administrative Cost

DBC: Downtown Business Committee

DEM: Division of Emergency Management (State of Florida)

DG: Douglas Galvan, Florida DEM

DH: David Hansen, Orange County Environmental Protection Division (EPD)

EPA: Environmental Protection Agency (Federal)

FEMA: Federal Emergency Management Agency (Federal)

FDEM: Florida Division of Emergency Management

FDEP: Florida Department of Environmental Protection (State of Florida)

FDOT: Florida Department of Transportation (State of Florida)

FRDAP: Florida Recreation Development Assistance Program (FDEP)

H-B: Hunton-Brady Architects.

HC: Hao Chau (Kimley-Horn and Associates)

HJH: HJ High

HR: Heather Ramos (Gray-Robinson)

HMGP: Hazard Mitigation Grant Program (FEMA/Florida DEM)

IDG: Innovative Design Group

IPO: Individual Project Order

JF: John Fitzgibbon, Town of Windermere

KHA: Kimley-Horn and Associates

LA: Liz Ardent, Town Council Member

LAS: Legacy Arborist Services

LMS: Local Mitigation Strategy (Orange County Office of Emergency Management)

MD: Mike Demko (Wade Trim)

MG: Mike Galura (Michael Galura Engineering Consultants)

MPO: Metropolitan Planning Organization

MW: Mike Woodward (Kimley-Horn and Associates)

MS4: Municipal Separate Storm Sewer System (USEPA acronym)

NOI: Notice of Intent

NPDES: National Pollutant Discharge Elimination System (EPA/FDEP)

NW: Nora White, Finance Director, Town of Windermere

PA: Public Assistance

PD: Police Department

PMP: Pavement Management Plan

PW: Public Works Department

PDCS: Town Permitting Consultant

RFP: Request for Proposals

RFQ: Request for Qualifications

RR: Railroad

ROW: Right-of-Way

SFWMD: South Florida Water Management District

STAR: State Annual Reporting (DEP)

SW: Stormwater

TAC: Transportation Advisory Committee.

TB: Tree Board

TC: Town Council







